

LOCATION OF WORK: FAI-290, I-290 EB RAMP - SANGAMON TO HARRISON AND DES PLAINES, COOK COUNTY, CITY OF CHICAGO

SUMMARY OF QUANTITIES

URBAN
90% FED.
10% STATE

CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	Y007	SIGN TRUSS Y002-1C
60602200	CONCRETE GUTTER	FOOT	10	10		
60602800	CONCRETE GUTTER, TYPE B	FOOT	160	160		
# 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	25		25	
# 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1		1	
63200310	GUARDRAIL REMOVAL	FOOT	353		353	
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	586		586	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
# 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	225	225		
# 66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1		
# 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,370	1,370		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	9,747	9,747		
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	1,788	1,788		
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	3,718	3,718		
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	436	436		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6,908	6,908		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,370	1,370		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,540	1,540		
# 72000300	SIGN PANEL - TYPE 3	SQ FT	693			693
# 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	693			693
# 73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	105			105
# 73400100	CONCRETE FOUNDATIONS	CU YD	9.0			9.0
# 73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	1			1
# 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,280	3,280		
# 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3,350	3,350		
# 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	231	231		
# 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	1,447	1,447		
# 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	32	32		
# 78100300	REPLACEMENT REFLECTOR	EACH	90	90		

* NON-PARTICIPATING ITEM - 100% STATE

@ Y000

SPECIALITY ITEM

URBAN
90% FED.
10% STATE

CODE NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	Y007	SIGN TRUSS Y002-1C
# 78200410	GUARDRAIL MARKERS, TYPE A	EACH	1	1		
# 78200520	BARRIER WALL MARKERS, TYPE B	EACH	48	48		
# 78200530	BARRIER WALL MARKERS, TYPE C	EACH	220	220		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,253	4,253		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	32	32		
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	200	200		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0017202	DOWEL BARS 1 1/2"	EACH	710	710		
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1	1		
Z0030070	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 3	EACH	1	1		
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2	2		
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
Z0067800	STEEL CASINGS 22"	FOOT	614	614		
Z0075310	TIE BARS 3/4"	EACH	881	881		
Z0075330	TIE BARS 1 1/4"	EACH	190	190		
# E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	180	180		
# K0029000	PERENNIAL PLANTS, WOODLAND TYPE	UNIT	5.1	5.1		
# K0029400	PERENNIAL PLANT SEDGE	UNIT	15	15		
XX005656	INLET FILTER CLEANING	EACH	38	38		
XX007035	CONTROLLED LOW-STRENGTH MATERIAL SPECIAL	CU YD	40.2	40.2		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	84	84		
# X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	200	200		
# X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	2	2		
X0323357	CONCRETE BARRIER REMOVAL AND REPLACEMENT	FOOT	80			80
Z0050360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	4			4
# X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
# X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	90	90		
# X8850102	INDUCTION LOOP	FOOT	139	139		
* XX004812	VIDEO TAPING OF SEWERS	FOOT	386	386		
* X0326294	STORM SEWERS TO BE CLEANED, HEAVY	FOOT	262	262		
X0326095	PIPE UNDERDRAIN REMOVAL AND REPLACEMENT	FOOT	72	72		
@ 20076600	TRAINEES	HOUR	500	500		

FILE NAME = 04_0168093_SHT_00082.dgn

USER NAME = #USER#
PLOT SCALE = 1:1
PLOT DATE = 12/12/2008

DESIGNED - BKS
DRAWN - BKS
CHECKED - AAC
DATE - 12/12/2008

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 10+00.00 TO STA. 25+67.92

F.A.I. RTE. 290 SECTION 2007-057 T COUNTY TOTAL SHEETS 60 4 CONTRACT NO. 60D93

ILLINOIS FED. AID PROJECT

Rev