



* SEE TYPICAL SECTIONS FOR THICKNESS AND MATERIALS

PAVEMENT PATCHING DETAILS

NOTES:

1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

SEQUENCE OF CONSTRUCTION

1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
2. REMOVE AND REPLACE FULL DEPTH PATCHES.
3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

FILE NAME =	USER NAME = 3690	DESIGNED - KF	REVISED -
S:\11-CADD\01-sh\26.D160093-SHT-DETAIL2.dgn		DRAWN - ED	REVISED -
PLOT SCALE = 1:1		CHECKED - AAC	REVISED -
PLOT DATE = Thursday, December 11, 2008		DATE - 12/12/2008	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

PAVEMENT PATCHING DETAILS

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 10+00.00 TO STA. 25+67.92

F.A.I. RTE. 290	SECTION 2007-057 T	COUNTY COOK	TOTAL SHEETS 60	SHEET NO. 26
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60D93	