

SUMMARY OF QUANTITIES			URBAN	100% FED
CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE	
			TOTAL QUANTITIES	1000-2A URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	40	40
40600300	AGGREGATE (PRIME COAT)	TON	270	270
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	4	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	948	948
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	364	364
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,583	6,583
42001300	PROTECTIVE COAT	SQ YD	618	618
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	119	119
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	846	846
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	67,171	67,171
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	119	119
44000600	SIDEWALK REMOVAL	SQ FT	846	846
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,475	1,475
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	1,814	1,814
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	610	610
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	214	214
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	750	750
▲ 55039700	STORM SEWERS TO BE CLEANED	FOOT	5,790	5,790
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	165	165
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	10	10
○ 20076600	TRAINING	HOOR	500	500

▲ NON-PART. (100% STATE)

○ Y080

SUMMARY OF QUANTITIES			URBAN	100% FED
CODE NO	ITEM	UNIT	CONSTRUCTION TYPE CODE	
			TOTAL QUANTITIES	1000-2A URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12,843	12,843
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3,630	3,630
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	53,986	53,986
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	14,340	14,340
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	932	932
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,986	1,986
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,281	4,281
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,815	1,815
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26,993	26,993
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	7,170	7,170
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	466	466
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	993	993
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	930	930
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	930	930
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,771	2,771
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,821	2,821
▲ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	193	193

\* SPECIALTY ITEM

FILE NAME = D168E22-sht-S00.dgn  
PLOT DATE = 1/29/2009

**CHRISTIAN-ROGE & ASSOCIATES, INC.**  
ENGINEERS-PLANNERS-SURVEYORS  
211 WEST WACKER DRIVE  
CHICAGO, ILLINOIS 60606  
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	K.R.K.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	S.J.P.	REVISED -	
DATE -	JANUARY 27, 2009	REVISED -	

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
DEMPSTER ST.

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
377	2008-003 RS	COOK	27	3
CONTRACT NO. 60E22				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT