F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	13 D-R-1-I	WILL	16	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

- - - CONTRACT NO. 60E89

URBAN 100% STATE

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE: SFTY-2A					
45000130	RELIEF JOINT	FOOT	53	53					
50102400	CONCRETE REMOVAL	CU YD	32.8	32.8					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.8	32.8					
50300300	PROTECTIVE COAT	SQ YD	5431	5431					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6180	6180					
50800515	BAR SPLICERS	EACH	36	36					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	109	109					
52000340	NEOPRENE EXPANSION JOINT 4"	FOOT	109	109					
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1					
~~70102640~~	~~TRAFFIC CONTROL AND PROTECTION, STANDARD 701801~~	~~L SUM~~	~~1~~	~~1~~					
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	11168	11168					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3719	3719					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	300	300					
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275					
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1200	1200					
78100300	REPLACEMENT REFLECTORS	EACH	50	50					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	388	388					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	18	18					
Z0010605	CLEANING DRAINAGE SYSTEM	L SUM	1	1					
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4					
Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4					
67000400	ENGINEER'S FIELD OFFICE TYPE A	CAL MO	3	3					
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	48	48					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
67100100	MOBILIZATION	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					

2/19/2009
c:\pw_work\PWIDOT\TINIAKOSMV\d0101671\8099-0264.dgn

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/19/2009