

CONTRACT NO. 60F07

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	464Y-RS-2	COOK	24	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	56	56					
40600300	AGGREGATE (PRIME COAT)	TON	280	280					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	22	22					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	507	507					
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	1710	1710					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5450	5450					
40603600	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N105	TON	1330	1330					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	55550	55550					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	13500	13500					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200					
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	150	150					
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SO YD	200	200					
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SO YD	400	400					
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	600	600					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	15	15					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	98	98					
60404940	FRAMES AND GRATES, TYPE 23	EACH	25	25					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	15	15					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	30	30					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9720	9720					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1236	1236					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18140	18140					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4740	4740					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	420	420					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2600	2600					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	920	920					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18140	18140					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4740	4740					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	420	420					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2600	2600					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	920	920					
* 78000900	THERMOPLASTIC PAVEMENT MARKING - ALKYD - LETTERS AND SYMBOLS	SO FT	1236	1236					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	920	920					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	920	920					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3549	3549					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	330	330					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2910	2910					
0 20076600	TRAINEES	HOUR	500	500					

* Specialty Items
 NP= Non-participating
 © 2080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

2/5/2009 10:42:10 AM E:\PROJECTS\60F07\60F07-3\SUMMARY.DWG