

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3592	0708 RS-3	COOK	15	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60F21

SUMMARY OF QUANTITIES			URBAN	100% FED	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	38	38					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	9	9					
40600300	AGGREGATE (PRIME COAT)	TON	44	44					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	50	50					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	133	133					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1891	1891					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	21853	21853					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	582	582					
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	554	554					
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	24	24					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	150	150					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5526	5526					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	134	134					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	23275	23275					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	105	105					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	135	135					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	50	50					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	875	875					

SUMMARY OF QUANTITIES			URBAN	100% FED	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 %STATE %FED.					
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	134	134					
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23275	23275					
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	105	105					
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	135	135					
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50	50					
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	410	410					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	946	946					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

1/31/2009 10:00 AM C:\WORK\KIP\PROJECTS\URBAN\SHEETS\88178.DWG

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
BRAINARD AVE.  
BURNHAM AVE. TO INDIANA STATE LN

PLOT DATE: 1/31/2009