

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	25		25
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	34		34
40600300	AGGREGATE (PRIME COAT)	TON	180		180
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	44		44
40600535	LEVELING BINDER (HAND METHOD), N70	TON	40		40
40600895	CONSTRUCTING TEST STRIP	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3,410		3,410
40600990	TEMPORARY RAMP	SQ YD	5,300		5,300
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,700		3,700
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	20		20
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	560		560
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	42,400		42,400
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	20		20
44000600	SIDEWALK REMOVAL	SQ FT	560		560
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	550		550
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	310		310
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	240		240
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	630		630
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,700		1,700
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	6		6
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5		5
60262700	INLETS TO BE RECONSTRUCTED	EACH	5		5
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	190		190
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		6
67100100	MOBILIZATION	L SUM	1		1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1

* DENOTES SPECIALTY ITEM
NP= Non-participating
© Y080

SUMMARY OF QUANTITIES				URBAN 100% FED.	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY		ROADWAY 1000-2A
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,350		3,350
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,400		2,400
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	39,300		39,300
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6,300		6,300
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	4,430		4,430
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7,650		7,650
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2,310		2,310
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11,300		11,300
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	800		800
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	13,100		13,100
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,100		2,100
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,475		1,475
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,550		2,550
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	770		770
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450		450
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	430		430
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,100		1,100
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154		154
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,300		2,300
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	190		190
Z0024478	FLEXIBLE DELINEATORS	EACH	7		7
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1

© 2007600 TRAINEES

HOURLY 500 500

FILE NAME = N:\PROJ\33291\33291_46\Design\Proposed\Plan\33291_46-03_Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60655
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = mready	DESIGNED - WBL	REVISED -
PLOT SCALE = 1:8000' / IN.	DRAWN - WBL	REVISED -
PLOT DATE = 2/4/2009	CHECKED - MJL	REVISED -
	DATE - 2/4/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US 12 / 45
WALNUT AVE TO US 12 (RAND RD)
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 330	SECTION 465 X-RS-1	COUNTY COOK	TOTAL SHEETS 19	SHEET NO. 3
FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT				
CONTRACT NO. 60F23				