

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A	
20200100	EARTH EXCAVATION	CU YD	52		52	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	20	20		
20400800	FURNISHED EXCAVATION	CU YD	20	20		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	564	564		
21400100	GRADING AND SHAPING DITCHES	FOOT	100	100		
25000210	SEEDING, CLASS 2A	ACRE	0.12	0.12		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	11		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	11		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	11		
25100630	EROSION CONTROL BLANKET	SQ YD	564	564		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	51	51		
40600300	AGGREGATE (PRIME COAT)	TON	256	256		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	50		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	570	570		
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	363	363		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	33		33	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6,244	6,208	36	
42001300	PROTECTIVE COAT	SQ YD	3,442	2,958	484	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	290	290		
44000086	HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE	SQ YD	347		347	
44000100	PAVEMENT REMOVAL	SQ YD	185		185	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	63,352	63,352		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	360		360	
44000300	CURB REMOVAL	FOOT	1,360	530	830	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	92	92		
44000600	SIDEWALK REMOVAL	SQ FT	290	290		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	7,986	7,986		
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	2,433	1,188	1,245	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,163	2,163		
44003100	MEDIAN REMOVAL	SQ FT	676	676		
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,000	1,000		
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	50	50		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	860	860		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	70	70		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	160	160		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	590	590		
50102400	CONCRETE REMOVAL	CU YD	47.7		47.7	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	48.6		48.6	
50300260	BRIDGE DECK GROOVING	SQ YD	330		330	
50300300	PROTECTIVE COAT	SQ YD	484		484	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,020		8,020	
50800515	BAR SPLICERS	EACH	68		68	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	140		140	
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,478	2,478		
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	22	22		
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2		

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000	SFTY-2A	
60254100	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	1	1		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	25	25		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	35	35		
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2		
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2		
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2		
60619121	CONCRETE MEDIAN, TYPE SB-6	SQ FT	1,660		1,660	
60619200	CONCRETE MEDIAN, TYPE SB-6.06	SQ FT	1,672	1,672		
60621911	CONCRETE MEDIAN, TYPE SM-2.06	SQ FT	314	314		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	4	2	
67100100	MOBILIZATION	L SUM	1	0.5	0.5	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	25,000	24,199	801	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,201	1,201		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48,212	36,408	11,804	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,012	4,012		
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,320	1,320		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	326	326		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	540	540		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,300	4,300		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	350		350	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,201	1,201		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36,408	35,832	576	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,012	4,012		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,320	1,320		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	326	326		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	520	520		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	706	706		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4		4	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	680	680		
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	840	840		
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	311		311	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52		
X0322879	GRADING AND SHAPING FORESLOPES	SQ YD	170	170		
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	232		232	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	11		11	
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	39	39		
X0712400	TEMPORARY PAVEMENT	SQ YD	185		185	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,661	2,661		
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	311		311	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	12		12	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	82	82		
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2		2	

\* SPECIALTY ITEM

FILE NAME = 0168F48-sht-500.dgn  
PLOT DATE = 3/6/2009



DESIGNED - G.F.L.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - MARCH 13, 2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES IL. RTE. 72 (TOUHY AVE. / HIGGINS RD.)			
SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA. VARIOUS	TO STA. VARIOUS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1350	2008-063 RS	COOK	42	3
CONTRACT NO. 60F40				
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT				