

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22
40600300	AGGREGATE (PRIME COAT)	TON	124	124
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	30	30
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	367	367
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	27	27
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3,035	3,035
42001300	PROTECTIVE COAT	SQ YD	92	92
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	26,718	26,718
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	160	160
44200998	CLASS B PATCHES, TYPE III, 12 INCH	SQ YD	75	75
44213100	PAVEMENT FABRIC	SQ YD	75	75
44213200	SAW CUTS	FOOT	132	132
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	448	448
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	96	96
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	128	128
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	590	590
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	320	320
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	100	100
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	42	42
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1,022	1,022
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A URBAN
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10,000	10,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	24,352	24,352
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	481	481
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	457	457
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	239	239
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	113	113
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,200	1,200
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	109.2	109.2
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24,352	24,352
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	481	481
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	457	457
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	239	239
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	113	113
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	519	519
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	519	519
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	442	442
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	70	70
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,336	1,336
Z0017202	DOWEL BARS 1 1/2"	EACH	80	80
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	61	61
© Z0076600	TRAINEES	Hour	500	500

© 4080
NP = Non-participating
* SPECIALTY ITEM