

# SUMMARY OF QUANTITIES

URBAN

				90% FED. 6.1% STATE 3.9% LAKE CO.			100% GURNEE	100% GURNEE
LOCATION OF WORK						U.S. RT. 41 (SKOKIE HWY.) @	*	*
				CONSTRUCTION CODE	Y031-1F	Y031-1F	Y031 3D	Y031 3D
SUMMARY OF QUANTITIES				GRAND TOTAL	STEARNS SCHOOL RD.	IL. RT. 21	STEARNS SCHOOL RD.	IL. RT. 21
CODE NO.	ITEM	UNIT						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6		3	3.00		
67100100	MOBILIZATION	L SUM	1		0.5	0.5		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		0.5	0.5		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		0.5	0.5		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1		0.5	0.5		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		0.5	0.5		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1		0.5	0.5		
** 72000200	SIGN PANEL - TYPE 2	SQ FT	60.0		15.0	45.0		
** 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	181.0		101.0	80.0		
** 78300400	THERMOPLASTIC PAVEMENT MARKING REMOVAL	SQ FT	362.0		202.0	160.0		
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	85.0		12.0	73.0		
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	173.0			173.0		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	298.0		95.0	203.0		
81400200	HEAVY-DUTY HANDHOLE	EACH	2			2		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	258.0		12.0	246.0		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		1	1		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1281				349	932
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3297.0		1074.0	2223.0		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	337.0		337.0			
87900200	DRILL EXISTING HANDHOLE	EACH	9		3	6		
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1			1		
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1		
87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1		1			
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1			1		
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	20.0			20.0		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	26.0		11.0	15.0		
88030050	SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10		6	4		
88030020	SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	9		5	4		
88030100	SIGNAL HEAD, L E D, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	3		3			
88030110	SIGNAL HEAD, L E D, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1		1			
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	13		6	7		
89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	4				1	3
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		1	1		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4		2	2		
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	154.2		77.1	77.1		
X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2		1	1		
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1281.0				349	932
X8808118	OPTICALLY PROGRAMMED SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1		
X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, L E D, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2			2		
X8808122	OPTICALLY PROGRAMMED SIGNAL HEAD, L E D, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1			1		
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	1		1			

\*\* Specialty Items  
\* VILLAGE OF GURNEE 100% RESPONSIBLE FOR COST

**RWA**  
 Regina Webster & Associates, Inc.  
 REGINA WEBSTER  
 AND ASSOC. INC.  
 CIVIL ENGINEERING CONSULTANTS  
 610 North Cicero Avenue, Suite 500  
 Chicago, Illinois 6023-1569