



TRAFFIC SIGNAL LEGEND

PROPOSED	EXISTING	PROPOSED	EXISTING

- CONSTRUCTION NOTES:**
- RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT, AND CONFIRMATION BEACON TO NEW MAST ARM. RELOCATION COST WILL BE INCLUDED IN THE COST OF NEW MAST ARM.
 - RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT, TO NEW TRAFFIC SIGNAL CONTROLLER. RELOCATION COST WILL BE INCLUDED IN THE COST OF NEW CONTROLLER.
 - RE-STRIPE EXISTING THERMOPLASTIC PAVEMENT MARKING STOP LINE WITH HIGH VISIBILITY THERMOPLASTIC PAVEMENT MARKING STOP LINE - 24".

RESTORATION OF WORK AREA, RESTORATION OF THE TRAFFIC SIGNAL WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEM SUCH AS FOUNDATION, CONDUIT, HANDHOLE, TRENCH AND BACKFILL, ETC., AND NO EXTRA COMPENSATION SHALL BE ALLOWED. ALL ROADWAY SURFACES SUCH AS SHOULDERS, MEDIAN, SIDEWALKS, PAVEMENT, ETC. SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD; AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDING IN ACCORDANCE WITH STANDARD SPECIFICATIONS 252 AND 250.

Existing sidewalk includes cobblestone pavers and any pavers damaged or removed as part of the proposed traffic signal work shall be replaced in kind.

FILE NAME =	USER NAME - #USER#	DESIGNED - NB/TCM	REVISED -
P:\P-08-1600-4\Design\1_87th at Kedzie\SH	\SHT009.DGN	DRAWN - NB/TCM	REVISED -
PLOT SCALE = 20.0000' / IN.	CHECKED - NB/TCM	REVISED -	REVISED -
PLOT DATE = 1/27/2009	DATE - 01/23/2009	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PROPOSED TRAFFIC SIGNAL PLAN
87TH STREET AT KEDZIE AVENUE**

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
395	2009-010 TS	COOK	11	9
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G08	