

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	68	68
40600300	AGGREGATE (PRIME COAT)	TON	387	387
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	60	60
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	701	701
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	174	174
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9,638	9,638
42001300	PROTECTIVE COAT	SQ YD	67	67
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	3,200	3,200
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	95,150	95,150
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,035	1,035
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	360	360
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	375	375
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	300	300
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1,560	1,560
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1,250	1,250
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1,200	1,200
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	656	656
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000 URBAN
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16,000	16,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	618.8	618.8
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80,801	80,801
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,087	2,087
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	5,091	5,091
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,795	1,795
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	187	187
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,500	1,500
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	618.8	618.8
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80,801	80,801
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,087	2,087
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	5,091	5,091
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,795	1,795
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	187	187
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,003	1,003
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,003	1,003
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,072	1,072
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	15	15
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,996	3,996
X7011015	TRAFFIC CONTROL AND PROTECTION, (EXPRESSWAYS)	L SUM	1	1
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	41	41

NP = Non-participating
* SPECIALTY ITEM

FILE NAME = D162012-ah-t-500.dgn
PLOT DATE = 2/5/2009



DESIGNED - G.F.L.	REVISED -
DRAWN - B.K.	REVISED -
CHECKED - M.P.	REVISED -
DATE - FEBRUARY 2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
US 30 / IL 56 TO KENDALL COUNTY LINE & RAMPS AT IL 47

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 44+40 TO STA. 231+68

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	2009-001 RS	KANE/KENDALL	37	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60G12	