

ROUTE: Sheridan Rd. (Martin Luther King Dr to IL 137)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT		REPAIR	
FROM	TO			PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	REPAIR AREA (SQ YD)
MLK Dr.	IL 137	SB		2	200	400	44
MLK Dr.	IL 137	SB		2	550	1100	122
MLK Dr.	IL 137	SB		24	5	120	13
MLK Dr.	IL 137	SB		24	5	120	13
MLK Dr.	IL 137	SB		2	80	160	18
MLK Dr.	IL 137	SB		2	1800	3600	400
MLK Dr.	IL 137	SB		2	1800	3600	400
MLK Dr.	IL 137	SB		20	20	400	44
MLK Dr.	IL 137	SB		2	300	600	67
MLK Dr.	IL 137	SB		2	880	1760	196
MLK Dr.	IL 137	SB		4	20	80	9
MLK Dr.	IL 137	SB		2	20	40	4
MLK Dr.	IL 137	SB		15	90	1350	150
MLK Dr.	IL 137	SB		12	25	300	33
MLK Dr.	IL 137	SB		12	50	600	67
MLK Dr.	IL 137	SB		2	12	24	3
MLK Dr.	IL 137	SB		2	12	24	3
MLK Dr.	IL 137	SB		2	12	24	3
MLK Dr.	IL 137	SB		2	25	50	6
MLK Dr.	IL 137	SB		2	20	40	4
MLK Dr.	IL 137	SB		2	30	60	7
MLK Dr.	IL 137	NB/SB		24	25	600	67
MLK Dr.	IL 137	NB		2	12	24	3
MLK Dr.	IL 137	NB		2	12	24	3
MLK Dr.	IL 137	NB		2	12	24	3
MLK Dr.	IL 137	NB		2	12	24	3
MLK Dr.	IL 137	NB		4	12	48	5
MLK Dr.	IL 137	NB		2	820	1640	182
MLK Dr.	IL 137	NB		2	80	160	18
MLK Dr.	IL 137	NB		2	40	80	9
MLK Dr.	IL 137	NB		24	5	120	13
MLK Dr.	IL 137	NB		36	5	180	20
MLK Dr.	IL 137	NB		2	25	50	6
MLK Dr.	IL 137	NB		2	780	1560	173
MLK Dr.	IL 137	NB		2	720	1440	160
MLK Dr.	IL 137	NB		24	5	120	13
MLK Dr.	IL 137	NB		2	45	90	10
MLK Dr.	IL 137	NB		2	250	500	56
MLK Dr.	IL 137	NB		2	440	880	98
MLK Dr.	IL 137	NB		2	300	600	67
MLK Dr.	IL 137	SB		2	15	30	3
MLK Dr.	IL 137	SB		12	25	300	33
MLK Dr.	IL 137	SB		12	10	120	13
MLK Dr.	IL 137	SB		12	25	300	33
MLK Dr.	IL 137	SB		36	6	216	24
MLK Dr.	IL 137	SB		2	20	40	4
MLK Dr.	IL 137	SB		12	15	180	20
MLK Dr.	IL 137	SB		12	2	24	3
MLK Dr.	IL 137	NB		15	2	30	3
MLK Dr.	IL 137	NB		2	100	200	22
MLK Dr.	IL 137	NB		12	25	300	33
MLK Dr.	IL 137	NB		2	12	24	3
MLK Dr.	IL 137	NB		2	100	200	22
MLK Dr.	IL 137	NB		24	15	360	40
MLK Dr.	IL 137	NB		12	2	24	3
MLK Dr.	IL 137	NB		24	2	48	5
MLK Dr.	IL 137	NB		12	12	144	16
MLK Dr.	IL 137	NB		12	4	48	5
MLK Dr.	IL 137	NB		24	2	48	5
MLK Dr.	IL 137	NB		24	2	48	5

TOTALS: 9976 FT 2816 SY

FILE NAME =	USER NAME = smthkl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE SHERIDAN ROAD</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
or\pwork\PW1001\SMITHKL\08125825\Designdgn		DRAWN -	REVISED -					VAR.	2009-018-PP	LAKE	22	14	
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	<b>CONTRACT NO. 60G17</b>		
PLOT DATE = 2/6/2009	DATE -	REVISED -			ILLINOIS FED. AID PROJECT								