ROUTE: IL 173 (From US 14 to IL 47)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
US 14	Altenberg Road	EB	1	18	8	144	16
		EB	1	12	4	48	5
		EB	1	12	4	48	5
Altenberg Road	Obrien Road	EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	6	72	8
		EB	1	12	4	48	5
		EB	1	12	4	48	5
Obrien	Oak Grove Road	EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
Oak Grove Road	Alden Road	EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	2	30	60	7
Alden Road	IL 47	EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	8	96	11
		EB	1	12	8	96	11
		EB	1	12	8	96	11
		EB	1	12	8	96	11
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	250	3000	333
		EB	1	12	4	48	5
		EB	1	12	4	48	5
		EB	1	12	4	48	5

ROUTE: IL 173 (From US 14 to IL 47)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
IL 47	Alden Road	WB	1	2	150	300	33
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	2	300	600	67
		WB	1	12	8	96	11
		WB	1	12	8	96	11
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
Alden Road	Obrien Road	WB	1	12	12	144	16
		WB	1	12	4	48	5
		WB	1	12	12	144	16
		WB	1	12	4	48	5
		WB	1	12	4	48	5
Obrien Road	Altenberg Road	WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
		WB	1	12	4	48	5
Altenberg Road	US 14	WB	1	12	4	48	5
		WB	1	18	8	144	16
		WB	1	12	4	48	5
		TOTALS:			1254 FT		1149 SY

FILE NAME = c:\pw_work\pwidot\smithkl\d0125047\Design.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/5/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 173

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-020 PP	MCHENRY	25	11

CONTRACT NO. 60G19

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT