

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-022 PP	WILL	41	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 60G21

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 100% FED 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27				
40600300	AGGREGATE (PRIME COAT)	TON	135	135				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	203	203				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	2698	2698				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7553	7553				
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	67434	67434				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	30273	30273				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	10091	10091				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	500	500				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	166500	166500				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2000	2000				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1000	1000				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	300	300				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2024	2024				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2024	2024				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1100	1100				
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	1491	1491				
20076600	TRANSSES	HOOR	500	500				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A				

* SPECIALTY ITEM
 0 Y080 (100% FED)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES

PLOT DATE: 2/5/2009

2/5/2009 4:54:19 PM User:wilgreendp