ROUTE: **IL129-Coal City Road to Hole in the Wall Road**

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Hole in the Wall Road	Coal City Road	NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	25	300.0	33.3
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	10	120.0	13.3
		NB	1-HMA	12	30	360.0	40.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	4	20	80.0	8.9
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	12	144.0	16.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	6	72.0	8.0
		NB	1-HMA	12	15	180.0	20.0
		NB	1-HMA	4	30	120.0	13.3
Coal City Road	Hole in the Wall Road	SB	1-HMA	4	100	400.0	44.4
		SB	1-HMA	4	100	400.0	44.4
		SB	1-HMA	4	75	300.0	33.3
		SB	1-HMA	4	50	200.0	22.2
		SB	1-HMA	4	30	120.0	13.3
		SB	1-HMA	4	50	200.0	22.2
		SB	1-HMA	4	12	48.0	5.3
		SB	1-HMA	12	30	360.0	40.0
		SB	1-HMA	6	50	300.0	33.3
		SB	1-HMA	4	40	160.0	17.8
		SB	1-HMA	12	6	72.0	8.0
		SB	1-HMA	4	50	200.0	22.2
		SB	1-HMA	4	100	400.0	44.4
		SB	1-HMA	4	50	200.0	22.2
		SB	1-HMA	12	6	72.0	8.0
		SB	1-HMA	12	6	72.0	8.0
TOTALS:					975 FT		638 SY

ROUTE: IL 129 (I-55 Bridge Approach to Strip Mine Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
I-55 Bridge Approach	Strip Mine Rd.	SB Lane 1	23 each	6	12	72	184
I-55 Bridge Approach	Strip Mine Rd.	NB Lane 2	30 each	6	12	72	240
TOTALS:					24 FT		424 SY

FILE NAME = c:\pw_work\PWIDOT\SMITHKL\d0125070\Design.dgn	USER NAME = smithkl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 129
		DRAWN -	REVISED -		
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -		SCALE: / SHEET NO. OF SHEETS / STA. / TO STA.
	PLOT DATE = 2/5/2009	DATE -	REVISED -		

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-022 PP	WILL	41	19
		CONTRACT NO. 60021		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		