ROUTE: 17th Ave from Cermak to I-290

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
Cermak	**I-290**	SB					
			1,2	22	30	660	73
			2	11	25	275	31
			1	11	25	275	31
			2	11	15	165	18
Lexington			1	11	75	825	92
			1	11	40	440	49
Harvard			2	11	35	385	43
			1,2	22	25	550	61
Roosevelt			2	11	100	1100	122
			1	11	45	495	55
13th			2	11	15	165	18
14th			1,2	22	40	880	98
			1	11	35	385	43
		NB					
Central			1,2	20	70	1400	156
			2	11	15	165	18
			2	11	50	550	61
14th Street			2	11	20	220	24
13th			2	11	15	165	18
Roosevelt Rd			2	11	12	132	15
			1,2	22	10	220	24
			2	11	15	165	18
Harvard			2	11	12	132	15
			2	11	15	165	18
Bataan Drive			1,2	20	30	600	67
		TOTALS:			769 FT		1168 SY

FILE NAME = c:\pw_work\PWIDOT\SMITHKL\d0125091\Design.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/9/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
17th Ave.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-025 PP	COOK	49	6

CONTRACT NO. 60G24

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT