ROUTE: Addison St. (0.1 Mile E/O of Oak Park Ave. to Cicero Ave.)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
ADDISON 5219	5212	EB	1	12	10	120	13
5212	5246	EB	1	12	10	120	13
5246	LOCKWOOD	WB	Bus Stop	12	100	1200	133
5250	5348	WB	1	12	20	240	27
5348	5416	WB	1	12	20	240	27
		EB	1	12	20	240	27
5416	5434	EB	1	12	20	240	27
		WB	1	12	20	240	27
5434	6110	WB	1	12	20	240	27
	LUNA	JOINT		6	75	450	50
	CENTRAL	JOINT		6	12	72	8
6110	6222	WB	1	12	20	240	27
6222	MOBILE	WB	1	12	20	240	27
MOBILE	6657	WB	1	12	12	144	16
		EB	1	12	6	72	8
		EB	1	10	10	100	11
		WB	1	12	6	72	8
	NEENAH	WB	1	8	100	800	89
6657	6615	WB	1	15	20	300	33
		WB	1	8	15	120	13
CICERO	4830	WB	2	12	250	3000	333
4830	4856	WB	1	12	20	240	27
		WB	2	12	20	240	27
4856 @ LAMON	4929	WB	1	12	12	144	16
		EB	1	12	12	144	16
4929	LAVERGNE	EB	1	15	12	180	20
		WB	1	12	25	300	33
LAVERGNE	LAMON	EB	1	6	100	600	67
5039	5031	EB	1	12	10	120	13
5121	5133	EB	1	20	30	600	67
5133	5146	EB	1	12	20	240	27
5146	5146	WB	2	12	100	1200	133
			TOTAL		1147 FT		1389 SY

FILE NAME = c:\pw_work\PWIDOT\SMITHKL\d0125091\Design.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/9/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
ADDISON ST.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-025 PP	COOK	49	11

CONTRACT NO. 60G24

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT