

ROUTE: SB&NB Cicero Ave from 31st to 87th

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
Omitted section 34th to 46th Street and @ I-55 Expy							
31st	87th	SB					
47th	Concrete Section		1,2,3	33	20	660	73
49th			3	11	10	110	12
Archer			1,2	22	20	440	49
			3	11	10	110	12
55th			3	11	20	220	24
			2	11	10	110	12
61st			2	11	10	110	12
63rd			3	11	10	110	12
65th			3	11	10	110	12
66th	Asphalt section		3	11	10	110	12
State Rd			3	11	15	165	18
73rd			1,3	22	30	660	73
			2	11	50	550	61
74th			1,2	22	50	1100	122
78th			2	11	40	440	49
79th			2	11	50	550	61
			2	11	75	825	92
83rd			2	11	100	1100	122
87th			1,2,3	33	150	4950	550
87th		NB	2	11	20	220	24
85th			2	11	40	440	49
83rd			2	11	30	330	37
			2,3	22	25	550	61
			1	11	25	275	31
			2	11	50	550	61
			1,3	22	25	550	61
79th			1,2,3	33	50	1650	183
			1	11	25	275	31
			1,2	22	30	660	73
78th			1,2	22	50	1100	122
76th			2	11	25	275	31
74th			2	11	15	165	18
73rd			2	11	35	385	43
			1,3	11	45	495	55
			1,2,3	33	35	1155	128
67th	Concrete section		2	11	10	110	12
65th			2	11	15	165	18
63rd			1,2,3	33	10	330	37
54th			1,2,3	33	10	330	37
50th			2	11	15	165	18

TOTALS: 1275 FT 2512 SY

FILE NAME =	USER NAME = emshkl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE CICERO AVE.</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\SMITHKL\08125091\Design.dgn	PLOT SCALE = 1/8" = 1' / IN.	DRAWN -	REVISED -					VAR.	2009-025 PP	COOK	49	32
	PLOT DATE = 2/9/2009	CHECKED -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.	<b>CONTRACT NO. 60G24</b>		
		DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				