

ROUTE: SB&NB Harlem Ave. (Ogden to 87th Street)

CROSS STREETS		DIRECTION (EB/WB NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
87th	Ogden Ave	NB	2	11	25	275	31
84th Street			2	11	200	2200	244
83rd			2	11	250	2750	306
81st			2	11	500	5500	611
79th			2	11	150	1650	183
			1	11	100	1100	122
Ogden	87th Street	SB	1,2	22	120	2640	293
Pershing Rd			1,2	22	25	550	61
			2	11	10	110	12
			2	11	15	165	18
Joliet Rd			2	11	20	220	24
43rd			2	11	45	495	55
46th			2	11	25	275	31
Forest			1,2	22	150	3300	367
			1,2	22	40	880	98
			2	11	25	275	31
			1	11	20	220	24
			2	11	25	275	31
Harlem over I-55 Bridge			1,2,3	33	150	4950	550
Hanover			1,2	22	50	1100	122
71st			2	11	25	275	31
73rd			2	11	200	2200	244
79th			1,2	22	30	660	73
80th			2	11	15	165	18
			2	11	45	495	55
83rd			2	11	50	550	61
			2	11	150	1650	183
			2	11	25	275	31
87th			2	11	150	1650	183
				12	12	144	16

TOTALS: 2647 FT 4110 SY

FILE NAME =	USER NAME = amthk1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE HARLEM AVE.</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwwork\pwidot\SMITHKL\d0125091\Design.dgn		DRAWN -	REVISED -					VAR.	2009-025 PP	COOK	49	34
PLOT SCALE = 1/8" = 1'-0"		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60G24				
PLOT DATE = 2/9/2009		DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				