

ROUTE: US 45 (119th Street to 111th Street )

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
119th Street	111th Street	NB	1	12	6	72	8
119th Street	111th Street	NB	1	12	50	600	67
119th Street	111th Street	NB	1	12	15	180	20
119th Street	111th Street	NB	1	12	6	72	8
119th Street	111th Street	NB	1	12	20	240	27
119th Street	111th Street	NB	1	12	6	72	8
119th Street	111th Street	NB	2	12	10	120	13
119th Street	111th Street	SB	1	12	6	72	8
119th Street	111th Street	SB	1	12	6	72	8
119th Street	111th Street	SB	1	12	300	3600	400
119th Street	111th Street	SB	1	2	200	400	44
119th Street	111th Street	SB	1	12	12	144	16
119th Street	111th Street	SB	1	2	300	600	67
119th Street	111th Street	SB	1	2	50	100	11
119th Street	111th Street	SB	1	2	100	200	22
119th Street	111th Street	SB	1	2	25	50	6
119th Street	111th Street	SB	1	2	50	100	11
119th Street	111th Street	SB	1	2	75	150	17
119th Street	111th Street	SB	1	2	25	50	6
119th Street	111th Street	SB	1	2	400	800	89
119th Street	111th Street	SB	1	2	200	400	44
119th Street	111th Street	SB	1	2	200	400	44
119th Street	111th Street	SB	2	12	6	72	8
119th Street	111th Street	SB	2	12	6	72	8
119th Street	111th Street	SB	2	12	6	72	8
119th Street	111th Street	SB	2	12	6	72	8
119th Street	111th Street	SB	2	12	50	600	67
119th Street	111th Street	SB	2	12	10	120	13
119th Street	111th Street	SB	2	12	15	180	20

TOTALS: 2167.0 1083.8  
FT SY

FILE NAME = c:\pw_work\PW100T\WILGREENP\d0125091\01.dgn	USER NAME = wilgreendp	DESIGNED - DRAWN -	REVISED - 7/17/08 - DPW REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE US 45</b>	F.A. RTE. VAR.	SECTION 2009-026 PP	COUNTY COOK	TOTAL SHEETS 30	SHEET NO. 22	CONTRACT NO. 60G25
PLOT SCALE = 100.0000' / IN.	PLOT DATE = 2/6/2009	CHECKED -	REVISED -	SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					