SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY (100% STATE)	CONSTRUCTION TYPE CODE: ROADWAY J000-2A	ROADWAY J000-2A	TRAFFIC SIGNAL IL RTE 21 Y031-3D	TRAFFIC SIGNAL IL RTE 21 Y031-3D	TRAFFIC SIGNAL EVP Y031-3D	TRAFFIC SIGNAL INTERCONNECT Y031-1F	NEW SIDEPATH SFTY-1B	INDIAN CREEK TRIBUTARY X028-2A
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	106	105	1						
M2510630	EROSION CONTROL BLANKET	SQ M	9,481	9,481							
M2520110	SODDING, SALT TOLERANT	SQ M	1,490	1,490							
M2520200	SUPPLEMENTAL WATERING	UNIT	194	193	1						
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	108	108							
M2810107	STONE RIPRAP, CLASS A4	SQ M	48								48
M2810109	STONE RIPRAP, CLASS A5	SQ M	330	330							
M2820200	FILTER FABRIC	SQ M	378	330							48
M3550500	HOT-MIX ASPHALT BASE COURSE, 200MM	SQ M	291	291							
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	2,025	2,025							
M4060300	AGGREGATE (PRIME COAT)	M TON	5	5							
M4060895	CONSTRUCTING TEST STRIP	EACH	1	1							
M4063080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	M TON	415							415	
M4063310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	M TON	243	35						208	
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	10,689	10,379	310						
M4205200	PROTECTIVE COAT	SQ M	22,733	22,405	328						
M4230200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 200MM	SQ M	458	458							
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK 125MM	SQ M	69	69							
M4402000	PAVEMENT REMOVAL	SQ M	15,881	15,881							
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	882	882							
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	2,184	2,184							
M4402420	MEDIAN REMOVAL	SQ M	1,454	1,454							
M4402530	PAVED SHOULDER REMOVAL	SQ M	172	172							
M4405000	PAVED DITCH REMOVAL	METER	167	167							
M5080105	REINFORCEMENT BARS	KG	16,190								16,190
M5090500	BICYCLE RAILING	METER	198		198						
M5120900	TEMPORARY SHEET PILING	SQ M	73.9								73.9
M5403000	CONCRETE BOX CULVERTS	CU M	137.7								137.7
M542H060	PIPE CULVERTS, CLASS A, TYPE 1 1050MM	METER	3	3							
M5429900	CONCRETE HEADWALLS	CU M	6.7	6.7							
M5500030	STORM SEWERS, CLASS A, TYPE 1 300MM	METER	219	219							
M5500040	STORM SEWERS, CLASS A, TYPE 1 375MM	METER	37	37							
M5500050	STORM SEWERS, CLASS A, TYPE 1 450MM	METER	75	75							
M5500430	STORM SEWERS, CLASS A, TYPE 2 300MM	METER	466	466							

* SPECIALTY ITEM

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-6	LAKE	149	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62519				

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAP ROUTE 337 (IL ROUTE 22)
SUMMARY OF QUANTITIES

SCALE: NONE DRAWN BY: TCK
DATE: 1/28/2009 CHECKED BY: DTH

PATRICK ENGINEERING INC. LISLE, ILLINOIS

P:\Lisle\IDOT\9171.A0\Drawings\RDWY\MiscSht\RdwS_SOFQ.dgn PDF(Grey_Large).plt 11:41:50 AM 2/6/2009 +Koeppen(Rdwy_Lisle)