

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-6	LAKE	149	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62519				

LOCATION STA. TO STA.	UNDERCUT AND PGE REPLACEMENT (CU M)		UNSUITABLE REMOVAL (TOPSOIL STRIPPING) (CU M)		EARTH EXCAVATION (CU M)		TOTAL SUITABLE EXCAVATION (CU M)		EXCAVATION TO BE USED IN EMBANKMENT (ADJ. FOR SHRINKAGE) 15% (CU M)		EMBANKMENT (CU M)		EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU M)	
	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II	STAGE I	STAGE II
	IL RTE. 22													
104+518 TO 104+525	0	0	4	0	8	0	8	0	7	0	0	0	7	0
104+525 TO 104+550	0	0	33	0	81	0	81	0	69	0	4	0	65	0
104+550 TO 104+575	0	0	41	0	94	0	94	0	80	0	8	0	72	0
104+575 TO 104+600	0	0	74	0	59	0	59	0	50	0	88	0	-38	0
104+600 TO 104+625	0	0	104	36	80	66	80	66	68	56	108	24	-40	33
104+625 TO 104+650	23	16	101	75	155	145	155	145	132	123	50	44	82	80
104+650 TO 104+675	46	36	98	79	180	165	180	165	153	140	44	24	109	117
104+675 TO 104+700	24	20	105	63	129	100	129	100	109	85	46	35	63	50
104+700 TO 104+725	0	0	114	41	76	19	76	19	65	16	49	59	16	-43
104+725 TO 104+750	0	0	123	36	129	19	129	19	109	16	25	51	84	-35
104+750 TO 104+775	0	0	131	18	238	49	238	49	202	41	5	24	197	18
104+775 TO 104+800	0	0	135	43	176	49	176	49	150	41	43	31	107	10
104+800 TO 104+825	0	0	70	43	201	183	201	183	171	155	41	31	130	124
104+825 TO 104+850	0	0	35	0	220	233	220	233	187	198	11	0	176	198
104+850 TO 104+875	0	0	69	38	104	111	104	111	88	95	25	23	63	72
104+875 TO 104+900	0	0	66	76	103	99	103	99	87	84	40	44	47	40
104+900 TO 104+925	0	0	65	68	100	98	100	98	85	83	53	45	33	38
104+925 TO 104+950	0	0	83	61	91	71	91	71	78	61	95	90	-17	-29
104+950 TO 104+975	0	0	99	66	93	44	93	44	79	37	219	118	-140	-80
104+975 TO 105+000	0	0	98	69	95	30	95	30	81	26	328	113	-247	-87
105+000 TO 105+025	0	0	99	73	80	20	80	20	68	17	329	171	-261	-154
105+025 TO 105+050	0	0	98	68	86	14	86	14	73	12	299	165	-225	-153
105+050 TO 105+075	0	0	99	66	81	5	81	5	69	4	369	95	-300	-91
105+075 TO 105+100	0	0	101	74	60	28	60	28	51	23	481	201	-430	-178
105+100 TO 105+132	0	0	116	98	71	72	71	72	60	61	585	487	-524	-425
105+197 TO 105+225	0	0	0	43	29	32	29	32	25	27	74	0	-49	27
105+225 TO 105+250	0	0	0	0	0	0	0	0	0	0	51	0	-51	0
105+250 TO 105+275	0	0	0	0	0	0	0	0	0	0	43	0	-43	0
105+275 TO 105+300	0	0	0	0	0	0	0	0	0	0	40	0	-40	0
105+300 TO 105+325	0	0	1	0	0	0	0	0	0	0	29	0	-29	0
105+325 TO 105+350	0	0	3	0	0	0	0	0	0	0	16	0	-16	0
105+350 TO 105+375	0	0	5	0	1	0	1	0	1	0	6	0	-5	0
105+375 TO 105+400	0	0	8	0	11	0	11	0	10	0	1	0	8	0
105+400 TO 105+425	0	0	11	0	16	0	16	0	14	0	1	0	13	0
105+425 TO 105+430	0	0	2	0	1	0	1	0	1	0	0	0	1	0
IL RTE. 22 SUBTOTALS	93	73	2,186	1,231	2,848	1,649	2,848	1,649	2,421	1,402	3,603	1,873	-1,182	-471
US RTE. 45/IL RTE. 21														
9+846 TO 9+875	0	0	55	26	98	82	98	82	83	69	34	16	49	53
9+875 TO 9+900	0	0	59	25	73	58	73	58	62	49	29	9	33	40
9+900 TO 9+925	0	0	58	30	50	39	50	39	43	33	34	15	9	18
9+925 TO 9+950	0	0	46	34	43	38	43	38	36	32	46	16	-10	16
9+950 TO 9+975	0	0	65	61	46	74	46	74	39	63	59	14	-19	49
9+975 TO 10+025	0	0	52	71	53	111	53	111	45	95	15	7	30	87
10+015 TO 10+025	0	0	1	3	109	48	109	48	92	41	1	2	91	38
10+025 TO 10+050	0	0	20	10	183	135	183	135	155	115	14	1	141	114
10+060 TO 10+075	0	0	21	13	48	79	48	79	41	67	18	20	23	47
10+075 TO 10+105	0	0	21	62	74	114	74	114	62	97	24	45	38	52
10+100 TO 10+109	0	0	0	12	24	45	24	45	20	38	6	2	14	36
10+109 TO 10+125	0	0	22	41	50	78	50	78	42	67	26	9	16	58
10+125 TO 10+128	0	0	10	18	13	15	13	15	11	12	8	6	3	6
10+128 TO 10+134	0	0	16	27	21	22	21	22	18	19	13	15	4	4
10+134 TO 10+150	0	0	47	82	60	62	60	62	51	52	39	57	12	-4
10+150 TO 10+156	0	0	18	30	19	18	19	18	16	16	17	27	-2	-11
10+156 TO 10+168	0	0	35	47	49	49	49	49	42	41	32	40	9	2
10+168 TO 10+180	0	0	37	36	65	65	65	65	55	55	28	23	27	32
US RTE. 45/IL RTE. 21 SUBTOTALS	0	0	583	626	1075	1130	1075	1130	914	961	443	325	471	636
TOTALS	93	73	2,769	1,858	3,923	2,780	3,923	2,780	3,335	2,363	4,046	2,197	-711	165

P:\Lisle\DOT\9171\A0\Drawings\RDWY\MII\Shts\RDV\Sched_02.dgn
 PDF(Grey_Large).plt
 +koeppen(Rdwy_Lisle)
 2/6/2009
 10:17:11 AM



EARTH EXCAVATION	STAGE I	STAGE II	TOTAL
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	3,923	2,780	6,703
POROUS GRANULAR EMBANKMENT, SUBGRADE	2,862	1,931	4,793
FURNISHED EXCAVATION	93	73	166
	711	0	711

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 FAP ROUTE 337 (IL ROUTE 22)
 SCHEDULE OF QUANTITIES

SCALE: NONE
 DATE: 1/28/2009

DRAWN BY: TCK
 CHECKED BY: DTH