F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	2021.1B-R	COOK	101	006
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62532				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	URBAN UNIT	TOTAL QUANTITY (100% FED. URBAN X771-2A)	ROADWAY	BRIDGE (1)	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS						
				CONSTRUCTION TYPE CODE										
44200112	PAVEMENT PATCHING, TYPE III, 9 INCH	SQ YD	100	100										
44200114	PAVEMENT PATCHING, TYPE IV, 9 INCH	SQ YD	50	50										
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	993	993										
50102400	CONCRETE REMOVAL	CU YD	41.3		41.3									
50104800	REMOVAL OF EXISTING CONCRETE DECK	L SUM	1		1									
50157300	PROTECTIVE SHIELD	SQ YD	1610		1610									
50200100	STRUCTURE EXCAVATION	CU YD	180		180									
50300225	CONCRETE STRUCTURES	CU YD	48.4		48.4									
50300255	CONCRETE SUPERSTRUCTURE	CU YD	525.9		525.9									
50300260	BRIDGE DECK GROOVING	SQ YD	1241		1241									
50300300	PROTECTIVE COAT	SQ YD	1730		1730									
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	11130		11130									
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	42		42									
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	107390		107390									
50800515	BAR SPLICERS	EACH	138		138									
50901730	BRIDGE FENCE RAILING	FOOT	517		517									
51500100	NAME PLATES	EACH	2		2									
52000110	PREFORMED JOINT STRIP SEAL	FOOT	340		340									
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	42		42									
52100520	ANCHOR BOLTS, 1"	EACH	168		168									
55100400	STORM SEWER REMOVAL 10"	FOOT	11	11										
58700300	CONCRETE SEALER	SQ FT	876		876									
59000200	EPOXY CRACK INJECTION	FOOT	75		75									
60202505	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID (CITY OF CHICAGO)	EACH	1	1										
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	18	18										
60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	10	10										
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	10	10										
60500050	REMOVING CATCH BASINS	EACH	1	1										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12										
67100100	MOBILIZATION	L SUM	1	1										
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1										

* DENOTES SPECIALTY ITEMS
☐ NON-PARTICIPATING

BRIDGE INFORMATION

(1) 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
111TH STREET OVER
F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
DATE: 01/16/09 CHECKED BY: ACL

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE., CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\TEMP\WA.DGN...\SUDOCUME.DGN...\SUDOCUMD.DGN
1-16-2009, 10:54:24 T:\DOCUMENT\09308600\CIVIL\DGN\SUDOCUME.DGN
HECHTER