

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% FED. URBAN	ROADWAY	BRIDGE	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE							
			X771-2A													
		TOTAL QUANTITY														
X701005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1												
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	224	224												
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLES	SQ FT	61	61												
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	502	502												
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1879	1879												
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1240	1240												
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1600	1600												
*72000100	SIGN PANEL - TYPE 1	SQ FT	24	24												
*72000200	SIGN PANEL - TYPE 2	SQ FT	11	11												
*72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	11	11												
*72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	43	43												
*73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2	2												
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	126	126												
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1856	1856												
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	621	621												
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	402	402												
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	130	130												
*78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	268	268												
*78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	836	836												
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	341	341												
*78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	100	100												
*78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	108	108												
*78200530	BARRIER WALL MARKERS, TYPE C	EACH	128	128												
78300100	PAVEMENT MARKING REMOVAL	SQ FT	963	963												
*81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	820			820										
*81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6" X 6" X 4"	EACH	12			12										
*81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	6			6										
*81700110	ELECTRIC CABLE IN CONDUIT, 600V, (EPR-TYPE RHW) 1/C NO. 10	FOOT	2860			2860										
*88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4					4								
*88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12					12								
*88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	2					2								

* DENOTES SPECIALTY ITEMS
 □ NON-PARTICIPATING

BRIDGE INFORMATION

① 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 111TH STREET OVER
 F.A.I ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
 DATE: 01/16/09 CHECKED BY: ACL

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 225 N. MICHIGAN AVE., CHICAGO, IL 60601
 TELEPHONE: 312/618-0000

\ATTORNEY\WALDON... \SUDDOQUE.DGN
 1/16/2009, 10:54:25
 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63
 HECHTBR