

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100% FED. URBAN X771-2A TOTAL QUANTITY	ROADWAY	BRIDGE ①	LIGHTING	CDOT LIGHTING	CDOT TRAFFIC SIGNALS	CONSTRUCTION TYPE CODE								
* 88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2					2									
* 88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	12					12									
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2					2									
□ X0320080	ROD AND CLEAN DUCT IN EXISTING CONDUIT SYSTEM	FOOT	652					652									
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	237	237													
* X0322679	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER	EACH	2					2									
* X0322683	CONCRETE FOUNDATION 24" DIA.	FOOT	54				18	36									
* X0322684	CONCRETE FOUNDATION 30" DIA.	FOOT	22					22									
* X0322701	SERVICE INSTALLATION, 100 AMP	EACH	1				1										
* X0322712	STREET NAME SIGN	EACH	7					7									
X0323080	DRAINAGE SCUPPERS, DS-12	EACH	6		6												
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	8			8											
X0324182	ELECTRICAL CABLE IN CONDUIT, TRIPLEX NO.6, 2-1C AND NO.8, 1-1C	FOOT	1550				1550										
X0324571	MAINTENANCE OF STREET LIGHTING SYSTEM (CITY OF CHICAGO)	L SUM	1				1										
X0324900	SERVICE CONNECTION TO CECO LINE	EACH	1				1										
X0324902	REMOVE EXISTING TRAFFIC SIGNAL FOUNDATION	EACH	7					7									
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	12			12											
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	2223		2223												
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	510				510										
* X0329888	REMOVE EXISTING STREET LIGHTING EQUIPMENT	L SUM	1				1										
* X0329890	SOLID STATE FULL-ACTUATED CONTROLLER, 4-PHASE DIGITAL TIMING WITH SOLID STATE TIME BASE COORDINATOR IN BASE MOUNTED CABINET	EACH	2					2									
* 81012600	CONDUIT IN TRENCH 2" DIA., PVC	FOOT	1100				1100										
* 81012800	CONDUIT IN TRENCH 3" DIA., PVC	FOOT	92					92									
* 81013000	CONDUIT IN TRENCH 4" DIA., PVC	FOOT	97					97									
* X0934800	MAST ARM, STEEL, MONOTUBE 20 FT.	EACH	3					3									
* X0934900	MAST ARM, STEEL, MONOTUBE 26 FT.	EACH	2					2									
* X0935100	MAST ARM, STEEL, MONOTUBE 35 FT.	EACH	2					2									
* X0935700	ELECTRIC CABLE IN CONDUIT NO. 12 19/C	FOOT	1277					1277									
* X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1					1									
* X0966510	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, MAST ARM MOUNTED	EACH	4					4									
* X0966520	SIGN, MESSAGE, ELECTRICALLY ILLUMINATED, FIBER OPTIC, BRACKET MOUNTED	EACH	4					4									

* DENOTES SPECIALTY ITEMS
 □ NON-PARTICIPATING

BRIDGE INFORMATION

① 111TH ST. OVER NB & SB I-57 S.N. 016-0989

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 111TH STREET OVER
 F.A.I. ROUTE 57 (INTERSTATE 57)

SUMMARY OF QUANTITIES

SCALE: N.T.S. DRAWN BY: BRH
 DATE: 01/16/09 CHECKED BY: ACL

TENG
 TENG & ASSOCIATES, INC.
 ENGINEERS/ARCHITECTS/PLANNERS
 229 N. MICHIGAN AVE., CHICAGO, IL 60601
 TELEPHONE: 312/616-0000

ATTENTION: SUDOCHE.DCN, SUDOCHE.DCN, SUDOCHE.DCN
 H6-2009, 10:44:26
 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63
 HEADLINE