

SUMMARY OF QUANTITIES				URBAN 100% FED.	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000	CONSTRUCTION TYPE CODE
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	46.4	46.4	
40600300	AGGREGATE (PRIME COAT)	TON	232.5	232.5	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	11.6	11.6	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1162	1162	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	3500	3500	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11362	11362	
42001300	PROTECTIVE COAT	SO YD	150	150	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	115936	115936	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000	
44002222	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 1/2"	SO YD	13900	13900	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	1700	1700	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	5200	5200	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	2200	2200	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	2500	2500	
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	1200	1200	
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	7	7	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	7	7	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	253	253	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	12	12	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	12	12	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	70	70	
** 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4704	4704	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2964.8	2964.8	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	119144	119144	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18660	18660	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	3000	3000	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	7406	7406	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2610	2610	

SUMMARY OF QUANTITIES				URBAN 100% FED.	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	1000	CONSTRUCTION TYPE CODE
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1482.4	1482.4	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	59572	59572	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	9330	9330	
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1500	1500	
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3703	3703	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1305	1305	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1839	1839	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1839	1839	
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3307	3307	
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	308.4	308.4	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4876	4876	
NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	253	253	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
• Z0074100	TRAINERS	HOUR	1,000	1,000	

• SPECIALTY ITEM  
 \*\* INCLUDES QUANTITY FOR FOUR (4) MESSAGE SIGNS, 3 MONTHS EACH, LOCATION TO BE DETERMINED BY THE ENGINEER.  
 NP = Non-participating  
 © 1988

PLOT DATE = 2/10/2009  
 FILE NAME = K:\1182534\cad\design\18251850.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = J.Treacy  
 MODEL = Default



200 West Front Street  
 Wheaton, IL 60187

DESIGNED - B.B.	REVISED -
DRAWN - J.T.T.	REVISED -
CHECKED - M.K.	REVISED -
DATE - 1/30/09	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

OAKTON STREET (DES PLAINES RIVER ROAD TO N CALDWELL AVE)  
 SUMMARY OF QUANTITIES  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 1332	SECTION (S071,3071A & 3072RS-3)	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 3
CONTRACT NO. 62755				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				