

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
535	118RS-4	LAKE	35	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO. 62779

SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	613	613					70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	82	82					70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1				
20400800	FURNISHED EXCAVATION	CU YD	484	484					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	927	927					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	26599	26599				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	13	13					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1368	1368				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	13	13					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	131060	131060				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	13	13					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5065	5065				
25100630	EROSION CONTROL BLANKET	SO YD	927	927					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	396	396				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	112	112					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1872	1872				
40600300	AGGREGATE (PRIME COAT)	TON	560	560					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	702	702				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	42	42					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1368	1368				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	131060	131060				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	489	489					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5065	5065				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	11747	11747					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	578	578				
42001300	PROTECTIVE COAT	SO YD	5	5					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1872	1872				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	139853	139853					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	702	702				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1273	1273				
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SO YD	2932	2932					* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	15	15				
44201867	CLASS D PATCHES, TYPE III, 18 INCH	SO YD	406	406					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1019	1019				
44201869	CLASS D PATCHES, TYPE IV, 18 INCH	SO YD	342	342					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2656	2656				
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SO YD	1148	1148					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	617	617				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4593	4593					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5506	5506				
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	18	18													
63200310	GUARDRAIL REMOVAL	FOOT	1417	1417													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1													

© 20076600 TRAINEES

Hour 500 500

© 4080
* Specialty Items

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/10/2009

2/10/2009 5:00 PM C:\WORK\PROJECTS\118RS-4\118RS-4-3.DWG