

CODE NUMBER	ITEM	UNIT	Roadway J000-2A		SFTY-3N IMPACT ATTENUATORS	Traffic Signals Y031-1F	HIGHWAY LIGHTING / ITS Y030-1E	Bridge SN 045-3166 X031-2A	Bridge SN 045-3164 X031-2A	Landscaping Y003	TOTAL QUANTITY
			STEARNS ROAD	IL RTE 25							
XX006723	TEMPORARY AGGREGATE BERM-RIPRAP	TON	582								582
XX006727	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	FOOT	2,400	100							2,500
XX006821	CONCRETE TRUCK WASHOUT	L SUM	1								1
* XX006937	GROUND ROD, 5/8" DIA, X 10 FT.	EACH					3				3
XX007023	STAINING CONCRETE STRUCTURES	SQ YD	200								200
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1								1
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	62,488	3,541							66,029
Z0013798	CONSTRUCTION LAYOUT	L SUM	1								1
Z0018000	DRAINAGE SCUPPERS (SPECIAL)	EACH						16			16
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	6								6
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	26								26
Z0018800	DRAINAGE SYSTEM	L SUM						1			1
Z0019600	DUST CONTROL WATERING	UNIT	302								302
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH			1						1
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH			1						1
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH			1						1
Z0034390	MODULAR EXPANSION JOINT 6"	FOOT						126			126
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1								1
Z0065745	SLOTTED DRAIN 12" WITH 2 1/2" SLOT	FOOT	20								20
Δ Z0076600	TRAINEES	HOUR	2,640	360							3,000
* XX007878	EROSION CONTROL BLANKET (SPECIAL 1)	SQ YD	22,351								22,351
* XX007879	EROSION CONTROL BLANKET (SPECIAL 2)	SQ YD	12,378								12,378
* XX007880	EROSION CONTROL BLANKET (SPECIAL 3)	SQ YD	16,027								16,027
XX007886	CLEARING (SPECIAL)	TON	200								200
* XX007887	DOCUMENTATION CAMERAS	L SUM	1								1
XX007888	DRAINAGE STRUCTURES TO BE ADJUSTED WITH A NEW TYPE 24 FRAME AND GRATE	EACH	20								20
* XX007889	5" RIGID GALVANIZED STEEL MULTI-DUCT W/ 4 1-1/4" INNER DUCT IN TRENCH	FOOT					1,450				1,450
* XX007894	5" RIGID GALVANIZED STEEL MULTI-DUCT W/ 4 1-1/4" INNER DUCT ATTACHED TO STRUCTURE	FOOT					3,880				3,880
XX007895	ROOFING SYSTEM	FOOT							534		534
* Z0005215	BITUMINOUS STABILIZATION STEEL PLATE BEAM GUARDRAIL	SQ YD	676	165							841
X024775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ YD	1,744								1,744
X024045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3								3

* Specialty Items

FILE NAME =
Seq-070793.01.SHT.dgn

USER NAME = GTINE

DESIGNED GT

REVISED -

DRAWN GT

REVISED -

PLOT SCALE = 1'

CHECKED MCW

REVISED -

PLOT DATE = 2/12/2009

DATE 01/16/09

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-20-BR	KANE	320	11
CONTRACT NO. 63075				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				