

GENERAL NOTES

1. The Contractor will not be allowed to set up a yard or field office on state property without written permission from the department or the villages.
2. It shall be the contractor's responsibility to verify all dimensions and conditions existing in the field prior to construction and ordering of materials.
3. The contractor shall contact the district one traffic control supervisor at (847) 705-4155 a minimum of 72 hours in advance of beginning work.
3. The contractor shall be required to provide access to abutting property at all times during the construction of this project.
4. Underbrush or debris at planting locations shall be removed and disposed of in accordance with section 201 of the standard specifications. This work will not be paid for separately, but the costs shall be considered as included in the contract unit prices for the construction items involved, and no additional compensation will be allowed.
5. The contractor shall protect all existing plant material from damage for which the contract does not provide removal. The protection of existing plant material and the repair or replacement of existing material damaged by the contractor shall be done in accordance with the requirements of section 201 of the standard specifications unless otherwise noted.
6. All perennial plant beds shall have all the sod removed and disposed from the bed prior to tilling the earth as described in article 254.07(b) of the standard specifications.
7. All perennials shall be planted 12" on center and mulched as described in article 245.08 of the standard specifications.
8. Pre-emergent granular herbicide shall be placed in mulched beds according to the special provisions.
9. Village water, sewer mains and other utilities may be located in the landscape area. The actual location of proposed landscaping will be adjusted in the field to avoid utilities. The villages of Worth, Palos hills, Chicago ridge, Oak lawn, Bridgeview, Burbank, and Bedford Park are not part of "J.U.L.I.E." The contractor shall contact the respective villages to locate their utilities.
10. The contractor will not be allowed to proceed with any planting work until all utility owners their facilities which may interfere with construction operations.
11. Interseeding, Class 2A is the be used to renovate areas where existing turf is in poor condition, Exact locations will be determined during the construction by the engineer.
12. Mulch placement 4" is to be placed around existing trees and shrubs in locations shown on plans or as directed by the engineer.
13. Where mulch beds are specified, all existing grass, weeds, and debris are to removed are the beds tilled to a depth of 6" prior to placing proposed plants. Following planting, beds are to be mulched to a depth of 3". The work be considered including in the contract unit price for the planting items.
14. Landscape Contractor shall verify all utility locations (existing and proposed) along with existing conditions and grades (existing and proposed), and note any discrepancies to owner, Engineer, and Landscape Architect immediately, before proceeding with any work.
15. Base information for these plans was taken from Engineer's site survey, geometric, and grading plans. Contractor shall verify all dimensions and locations of existing and proposed features, and familiarize themselves with any obstacles encumbering the installation of this project.

16. Any existing tree surveys or locations for these plans were prepared by the Engineer or a certified arborist. See plans for information.

F. A. U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
348	07-00055-00-LS	COOK	41	20
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT #63106

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**FAP 348 (HARLEM AVENUE)
PLANT SPECIFICATION**

SCALE: VERT. NA
HORIZ. NA
DATE 12-19-08

DRAWN BY MJD
CHECKED BY R/JW/PKB