

EARTHWORK SCHEDULE						
STATION	20200100		20201200		EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	EARTH EXCAVATION	EARTH EXCAVATION VOLUME USED (15% SHRINKAGE)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL			
LINE "ALLENDALE"	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
102+50 TO 103+00	50	42	21	3	39	
103+00 TO 103+50	60	51	41	10	41	
103+50 TO 104+00	78	66	45	14	53	
104+00 TO 104+50	100	85	49	17	68	
104+50 TO 105+00	114	97	53	21	75	
105+00 TO 105+50	112	95	57	28	67	
105+50 TO 106+00	69	58	55	81	-23	
106+00 TO 106+50	16	14	43	206	-193	
106+50 TO 106+54	0	0	3	24	-24	
SW BRIDGE CONE	0	0	0	30	-30	
NW BRIDGE CONE	0	0	0	14	-14	
WEST ABUTMENT	53	45	0	0	45	
EAST ABUTMENT	53	45	0	0	45	
SE BRIDGE CONE	0	0	0	12	-12	
NE BRIDGE CONE	0	0	0	31	-31	
107+48 TO 107+50	0	0	2	25	-25	
107+50 TO 108+00	0	0	63	606	-606	
108+00 TO 108+50	0	0	85	716	-716	
108+50 TO 109+00	0	0	86	687	-687	
109+00 TO 109+50	0	0	67	449	-449	
109+50 TO 110+00	11	9	47	164	-154	
110+00 TO 110+50	55	46	42	43	4	
110+50 TO 111+00	78	66	38	13	53	
111+00 TO 111+50	55	47	20	4	42	
TOTALS	903	768	818	3,200	-2,433	

SUMMARY		
20200100	20400800	20201201
EARTH EXCAVATION	FURNISHED EXCAVATION	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
(CU YD)	(CU YD)	(CU YD)
910	2,500	820

FILE NAME = m:\pco\3335\design\proposed\plan\3335-05-SCHEDULE.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = ntumbv	DESIGNED - MWR	REVISED -
	DRAWN - MWR	REVISED -
PLOT SCALE = 1/8000' / IN.	CHECKED - MJL	REVISED -
PLOT DATE = 2/6/2009	DATE - 10/31/2008	REVISED -

**McHENRY COUNTY
DIVISION OF TRANSPORTATION**

**TR 73 ALLENDALE ROAD
OVER VANDER KARR CREEK
EARTHWORK SCHEDULES**

SCALE: N.T.S. SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE. 73	SECTION 05-00310-00-BR	COUNTY McHENRY	TOTAL SHEETS 44	SHEET NO. 5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 63114	