

SUMMARY OF QUANTITIES

| CODE NO. | PAY ITEM | UNIT | CONSTRUCTION CODE 1000 |
|----------|--|--------|---------------------------|
| 35101600 | AGGREGATE BASE COURSE, TYPE B 4" | SQ YD | 59 |
| 40600100 | BITUMINOUS MATERIALS (PRIME COAT) | GALLON | 3,357 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 69 |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 631 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 2 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 1,233 |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 1,600 |
| 44000159 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2" | SQ YD | 16,785 |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 175 |
| 44201705 | CLASS D PATCHES, TYPE II, 5 INCH | SQ YD | 129 |
| 44201709 | CLASS D PATCHES, TYPE III, 5 INCH | SQ YD | 328 |
| 44201711 | CLASS D PATCHES, TYPE IV, 5 INCH | SQ YD | 735 |
| 44201718 | CLASS D PATCHES, TYPE II, 6 1/2 INCH | SQ YD | 82 |
| 44201721 | CLASS D PATCHES, TYPE III, 6 1/2 INCH | SQ YD | 199 |
| 44201724 | CLASS D PATCHES, TYPE IV, 6 1/2 INCH | SQ YD | 434 |
| 44201741 | CLASS D PATCHES, TYPE II, 8 INCH | SQ YD | 108 |
| 44201745 | CLASS D PATCHES, TYPE III, 8 INCH | SQ YD | 215 |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 394 |
| 44300100 | AREA REFLECTIVE CRACK CONTROL TREATMENT | SQ YD | 16,785 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 387 |
| 67100100 | MOBILIZATION | LSUM | 1 |

| CODE NO. | PAY ITEM | UNIT | CONSTRUCTION CODE 1000 |
|------------|--|-------|---------------------------|
| 70101700 | TRAFFIC CONTROL AND PROTECTION | LSUM | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 13,239 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 1,486 |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 293 |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 18,052 |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 1,235 |
| * 78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 1,032 |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 78 |
| X4420092 | CLASS D PATCHES, TYPE II, 9 1/2 INCH | SQ YD | 32 |
| X4420093 | CLASS D PATCHES, TYPE III, 9 1/2 INCH | SQ YD | 95 |
| X4420099 | CLASS D PATCHES, TYPE IV, 9 1/2 INCH | SQ YD | 190 |
| X4420452 | CLASS D PATCHES, TYPE II, 4 INCH | SQ YD | 64 |
| X4420454 | CLASS D PATCHES, TYPE III, 4 INCH | SQ YD | 128 |
| X4420456 | CLASS D PATCHES, TYPE IV, 4 INCH | SQ YD | 234 |
| △ Z0076600 | TRAINEES | Hour | 500 |

* SPECIALTY ITEMS

△ Y080

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

| LOCATION | AREA (SQ YD) |
|--|--------------|
| CRYSTAL LAKE AVENUE (STA 13+45) | 50 |
| ELEMENTARY SCHOOL DRIVEWAY (STA 17+04.5) | 125 |
| ELEMENTARY SCHOOL DRIVEWAY (STA 19+90) | 145 |
| JR HIGH DRIVEWAY (STA 23+10) | 200 |
| GRAVEL DRIVEWAY (STA 26+18) | 11 |
| FIRE DEPARTMENT DRIVEWAY (STA 29+04) | 94 |
| HMA DRIVEWAY (STA 29+78) | 11 |
| FIRE DEPARTMENT EAST DRIVEWAY (STA 30+58) | 27 |
| FOXFORD HILLS MAINTENANCE DRIVEWAY (STA 31+02) | 24 |
| HMA DRIVEWAY (STA 32+36) | 12 |
| HMA DRIVEWAY (STA 34+39) | 34 |
| HMA SERVICE DRIVEWAY (STA 35+38) | 20 |
| FOXFORD DRIVE (STA 36+90) | 80 |
| MCCD PARKING LOT DRIVEWAY (STA 37+95) | 54 |
| BIKEPATH (STA 51+09) | 296 |
| CRYSTAL LAKE AVENUE (STA 53+30) | 50 |
| TOTAL | 1,233 |

COPYRIGHT © 2008 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS PROFESSIONAL ENGINEER EXAMINATION BOARD
 EXAMINATION NO. 48831C
 DATE: 2/11/2009
 TIME: 11:55:55 AM
 PROJECT: ILLINOIS STATE HIGHWAY 150
 DRAWING: STP (LAPP) IMPROVEMENTS SHEETS 080936-0001.SHT



| | |
|-----------------|--------------------------------|
| DESIGNED - MWP | REVISED - IDOT REVIEW 02/03/09 |
| DRAWN - CJC | REVISED - |
| CHECKED - RWL | REVISED - |
| DATE - 10/29/08 | FILE - 080936-soq.sht |

VILLAGE OF CARY, ILLINOIS
CRYSTAL LAKE AVENUE
STP (LAPP) IMPROVEMENTS

SUMMARY OF QUANTITIES AND
SCHEDULE OF QUANTITIES

SCALE: NONE

STA. TO STA.

| | | | | |
|--|----------------|--------------------|--------------|-----------|
| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 0116 | 08-00055-00-RS | McHENRY | 18 | 3 |
| FED. ROAD DIST. NO. 1 | | CONTRACT NO. 63115 | | |
| JOB NO. C-91-202-09 ILLINOIS FED. AID PROJECT M-9003 (169) | | | | |