

INDEX OF SHEETS

1. COVER SHEET
2. SUMMARY OF QUANTITIES, INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES
3. TYPICAL SECTIONS
4. EXISTING PLAN
5. PROPOSED SIDEWALK, PAVEMENT MARKING, AND BUS LANE PLAN
6. DISTRICT 1 TYPICAL PAVEMENT MARKINGS

STATE STANDARDS

424001-05	CURB RAMPS FOR SIDEWALKS
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701001-02	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' (4.5m) AWAY
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5m) TO 24" (600mm) FROM PAVEMENT EDGE
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701311-03	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
701801-04	LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
720001-01	SIGN PANEL MOUNTING DETAILS
720006-02	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
729001-01	APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)

GENERAL NOTES:

EXISTING VILLAGE OWNED AND MAINTAINED UTILITY LINES ARE SHOWN ON THE PLANS TO INDICATE THEIR PRESENCE AND APPROXIMATE LOCATION. THE CONTRACTOR SHALL NOTIFY THE VILLAGE OF DOLTON PUBLIC WORKS DEPARTMENT (708) 201-3235 TWO WEEKS PRIOR TO COMMENCING ANY EXCAVATION IN THE VICINITY OF THIS LINES. THE VILLAGE WILL THEN LOCATE AND MARK THE HORIZONTAL LOCATIONS OF THE LINES AND PROVIDE ANY AVAILABLE INFORMATION AS TO THEIR DEPTH. SHOULD ANY OF THE LINES BE DAMAGED BY THE CONTRACTOR'S OPERATION, THE CONTRACTOR SHALL REPAIR THEM TO THE SATISFACTION OF THE ENGINEER AND AT NO COST TO THE VILLAGE/STATE.

UTILITY LINES WERE PLOTTED FROM INFORMATION FURNISHED BY THE VARIOUS UTILITY COMPANIES INVOLVED AND THE ACCURACY SHOULD BE CONSIDERED APPROXIMATE ONLY.

UTILITY COMPANIES MAY BE ADJUSTING THEIR FACILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL COOPERATE WITH THESE ORGANIZATIONS WHILE THESE ADJUSTMENTS ARE BEING PREFORMED. J.U.L.I.E.-JOINT UTILITY LOCATION INFORMATION FOR EXCAVATORS SYSTEM (800) 892-0123 OR 811.

SIDEWALK SLOPES SHALL NOT EXCEED A 2% CROSS SLOPE, 5% LONGITUDINAL SLOPE.

ALL GRASSED AREAS DISTURBED BY CONSTRUCTION OPERATIONS, INCLUDING LOCATIONS WHERE SIDEWALK IS TO BE REMOVED AND NOT REPLACED ARE TO BE RESTORED WITH TOPSOIL FURNISH AND PLACE, 4", NITROGEN, PHOSPHORUS AND POTASSIUM NUTRIENTS, AND SODDING, SALT TOLERANT AS DEPICTED IN THE SUMMARY OF QUANTITIES.

ALL PROPOSED SIGN PANELS SHALL HAVE TYPE AZ REFLECTORIZED SHEETING.

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE			
					I000	SFTY-1D	Y002-1C	Y003
	20200100	EARTH EXCAVATION	CU YD	89	89			
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	235				235
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3				3
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	3				3
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	3				3
	25200110	SODDING, SALT TOLERANT	SQ YD	235				235
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	237	237			
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	90	90			
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	27	27			
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	13	13			
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10	10			
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1976	1976			
	42400800	DETECTABLE WARNINGS	SQ FT	64	64			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	141	141			
	44000600	SIDEWALK REMOVAL	SQ FT	410	410			
	60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1			
	60601005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	15	15			
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	119	119			
	67100100	MOBILIZATION	L SUM	1	1			
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
	72000100	SIGN PANEL - TYPE 1	SQ FT	6.0			6.0	
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2			2	
	72900200	METAL POST - TYPE B	FOOT	24			24	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	220		220		
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	127		127		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	200		200		
	X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	87	87			
	X7240505	RELOCATE SIGN PANEL AND POST	EACH	1			1	
	XX001011	BICYCLE RACKS	EACH	1	1			

* - INDICATES SPECIALTY ITEMS

FILE NAME = 06612_02-INDX-01	USER NAME =	DESIGNED -- MPN	REVISED --	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DORCHESTER AVENUE SIDEWALK CONSTRUCTION AND BUS LOADING ZONE EXTENSION SUMMARY OF QUANTITIES, INDEX OF SHEETS, STATE STANDARDS, & GENERAL NOTES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		CHECKED -- JAK	REVISED --						06-00162-02-SW	COOK	6	2	
	PLOT SCALE =	DRAWN -- RG	REVISED --			SCALE: NONE	SHEET NO. 2	OF 6	SHEETS	STA.	TO STA.	CONTRACT NO. 63119	
	PLOT DATE = 12-23-08	CHECKED -- MPN	REVISED --			FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT CMM-9003(079)				