

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
299I	08-00095-02-PV	DUPAGE	55	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

DRAINAGE QUANTITIES

LOCATION	STA.	OFFSET	LT OR RT	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID (60218400)	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 11 FRAME & GRATE (60224020)	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME & GRATE (60219300)	INLETS, TYPE A, TYPE 11 FRAME AND GRATE (60236800)	INLETS, TYPE B, TYPE 11 FRAME AND GRATE (60240310)	INLETS, TO BE ADJ. W/ TYPE 3 FRAME AND GRATE (60260500)	INLETS, TO BE ADJ. W/ TYPE 11 FRAME AND GRATE (60261300)
				(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
	168+42.85	13.00	LT				1			
	168+66.84	16.46	RT	1						
	168+67.96	38.43	LT			1				
	168+96.38	37.91	LT				1			
	169+23.13	15.68	RT					1		
	169+23.88	15.77	LT				1			
	172+11.87	65.00	RT				1			
	172+13.66	66.79	LT				1			
	172+51.87	65.00	RT			1				
	172+53.66	66.79	LT			1				
	173+91.38	27.42	RT	1						
	174+02.36	17.00	RT					1		
	174+10.10	17.00	LT				1			
	175+71.91	39.31	LT				1			
	175+96.09	39.31	LT					1		
	176+03.61	27.26	RT	1						
	176+04.20	20.54	LT			1				
	176+23.00	12.70	LT							1
	176+23.55	12.00	LT				1			
	182+02.03	12.00	LT				1			
	182+02.03	12.00	RT					1		
	182+36.39	37.63	LT				1			
	182+62.78	37.34	LT		1					
	182+64.28	40.20	RT	1						
	182+84.70	12.00	RT					1		
	182+84.70	12.00	LT				1			
	187+94.00	12.70	LT							1
	187+94.00	12.30	RT							1
	189+48.00	12.60	LT					1		
	198+51.00	13.50	LT					1		
	198+53.00	12.40	RT					1		
	215+12.00	13.20	LT							1
	215+13.00	12.10	RT					1		

LOCATION	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)
	44000100	44000198
RECONSTRUCTION SECTIONS		
STA. 168+00.00 TO STA. 190+75.00	7.873	---
RESURFACING SECTIONS:		
STA. 190+75.00 TO STA. 215+40.95	---	7.131

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
PRAIRIE AVENUE RECONSTRUCTION
 SCHEDULES OF QUANTITIES

SCALE: N.T.S.
 DATE: 11/21/2008

DRAWN BY MTH
 CHECKED BY DJL