

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES		80% FED / 20% STATE		Y007 COUNTY	
CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	JO DAVIESS	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	297	297	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	555	555	
20100500	TREE REMOVAL, ACRES	ACRE	1.50	1.50	
20200100	EARTH EXCAVATION	CU YD	25,975	25,975	
20200200	ROCK EXCAVATION	CU YD	15	15	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	100	100	
* 25000100	SEEDING, CLASS 1	ACRE	0.25	0.25	
* 25000210	SEEDING, CLASS 2A	ACRE	7.25	7.25	
* 25000310	SEEDING, CLASS 4	ACRE	3.25	3.25	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	947	947	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	947	947	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	947	947	
* 25000750	MOWING	ACRE	7.50	7.50	
* 25100115	MULCH, METHOD 2	ACRE	10.50	10.50	
* 25100630	EROSION CONTROL BLANKET	SQ YD	18,710	18,710	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	8,422	8,422	
28000300	TEMPORARY DITCH CHECKS	EACH	97	97	
28000400	PERIMETER EROSION BARRIER	FOOT	6,363	6,363	
28000500	INLET AND PIPE PROTECTION	EACH	24	24	
28100107	STONE RIPRAP, CLASS A4	SQ YD	449	449	
28200200	FILTER FABRIC	SQ YD	533	533	
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	83	83	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	962	962	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2,190	2,190	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	449	449	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	428	428	
44002600	GUTTER OUTLET REMOVAL	FOOT	202	202	
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	852	852	
48100100	AGGREGATE SHOULDERS, TYPE A	TON	3,420	3,420	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	4,013	4,013	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	2	2	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1	

* SPECIALTY ITEM ■ NON-PARTICIPATING