

# SCHEDULE OF QUANTITIES

1	LT STA	436 +15	80.00'
1	RT STA	436 +40	45.00'
1	RT STA	436 +75	33.00'
1	LT STA	436 +80	33.00'
1	LT STA	447 +25	35.16'
1	RT STA	447 +60	36.00'
1	LT STA	448 +00	105.00'
1	RT STA	448 +20	65.00'
1	LT STA	448 +25	105.00'
1	LT STA	448 +55	65.00'
1	RT STA	448 +55	65.00'
1	LT STA	449 +00	65.00'
1	LT STA	449 +20	34.34'
1	RT STA	449 +20	36.90'
1	LT STA	483 +50	33.00'
1	LT STA	484 +00	55.00'
1	RT STA	484 +00.01	33.00'
1	RT STA	484 +07.68	50.00'
1	LT STA	485 +00	55.00'
1	RT STA	485 +00	50.00'
1	LT STA	485 +30	33.00'
1	RT STA	485 +75	33.00'
1	RT STA	500 +40	33.00'
1	LT STA	500 +50	33.00'
1	LT STA	500 +75	55.00'
1	RT STA	501 +20	50.00'
1	RT STA	501 +50	50.00'
1	RT STA	501 +68.26	43.79'
1	RT STA	501 +68.68	33.00'
1	LT STA	503 +00	55.00'
1	LT STA	503 +19.58	32.79'
<hr/>			
147	SUB-TOTAL		

Willow Road			
1	LT STA	40 +60	80.00'
1	LT STA	41 +50	80.00'
1	RT STA	42 +11.65	25.25'
1	LT STA	42 +69	24.80'
<hr/>			
4	SUB-TOTAL		
151	GRAND TOTAL		

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	REMARKS
13	Various	1 AT EACH CULVERT / 2 @ SN 043-1062
<hr/>		
13	TOTAL	

70106700 TEMPORARY RUMBLE STRIP

EACH	LOCATION
Carroll County	
Sta Equation: Sta 1030+92.44 BK = Sta 0+00.00 AH	
1	RT STA 1015 +56.88
1	RT STA 1020 +56.88
1	RT STA 1025 +56.88
<hr/>	
Jo Daviess County	
1	LT STA 15 +32
1	LT STA 20 +32
1	LT STA 25 +32
<hr/>	
6	TOTAL

70300520 PAVEMENT MARKING TAPE, TYPE III 4"

FOOT	LOCATION	REMARKS
610.5	RT STA 1 +83 - 7 72	SN 043-1062 (Stage 3) - White
548.6	LT STA 2 +24.91 - 7 72	SN 043-1062 (Stage 2) - White
424.7	LT STA 2 +77 - 7 01	SN 043-1062 (Stage 3) - White
342.0	RT STA 3 +21 - 6 62.70	SN 043-1062 (Stage 2) - White
<hr/>		
1,926	TOTAL	

70300570 PAVEMENT MARKING TAPE, TYPE III 24"

FOOT	LOCATION	REMARKS
8.8	RT STA 1 +64.44	SN 043-1062 (Stop Bar) - White
9.9	LT STA 8 +32	SN 043-1062 (Stop Bar) - White
<hr/>		
19	TOTAL	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	REMARKS
17.6	RT STA 1 +64.44	SN 043-1062 (Stop Bar)
203.5	RT STA 1 +83 - 7 72	SN 043-1062 (Edge Line)
182.9	LT STA 2 +24.91 - 7 72	SN 043-1062 (Edge Line)
141.6	LT STA 2 +77 - 7 01	SN 043-1062 (Edge Line)
114.0	RT STA 3 +21 - 6 62.70	SN 043-1062 (Edge Line)
19.8	LT STA 8 +32	SN 043-1062 (Stop Bar)
<hr/>		
679	TOTAL	

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
275	STA 3 +49 - 6 23	SN 043-1062 (Stage 2)
25	STA 3 +24 - 3 49	SN 043-1062 (Stage 3)
25	STA 6 +23 - 6 48	SN 043-1062 (Stage 3)
<hr/>		
325	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	REMARKS
275	STA 3 +49 - 6 23	SN 043-1062 (Stage 3)
<hr/>		
275	TOTAL	