

# SCHEDULE OF QUANTITIES

**Z0025519 DRAIN FOR AGGREGATE BASE COURSE**

SQ YD	LOCATION	REMARKS
1.2	RT/LT STA 41 + 25	WILLOW ROAD
1.5	RT/LT STA 89 + 00	BETHEL ROAD
2.7	TOTAL	

**Z0005400 BREAKER-RUN CRUSHED STONE**

TON	LOCATION	REMARKS
92.0	STA 182 + 98.97	18" Additional Bedding Depth/24" Total
12.9	LT/RT STA 278 + 24.12	* 6" Additional Bedding Depth/12" Total
1.3	LT/RT STA 336 + 17.63	* 6" Additional Bedding Depth/12" Total
32.6	STA 404 + 70.72	12" Additional Bedding Depth/18" Total
3.1	LT/RT STA 435 + 71.80	* 6" Additional Bedding Depth/12" Total
36.1	STA 448 + 28.40	6" Additional Bedding Depth/12" Total
79.8	STA 484 + 22.22	6" Additional Bedding Depth/12" Total
133.0	STA 501 + 14.74	18" Additional Bedding Depth/24" Total
391	TOTAL	

\* \*\*\*\* NOTE: ADDITIONAL BEDDING IS FOR END SECTION(S) AND/OR DROP BOX ONLY (INSERTION CULVERT LINER LOCATION)

**Z0023600 FILLING EXISTING CULVERTS**

EACH	LOCATION	REMARKS
1	STA 240 + 05.36	PLUG EXISTING
1	STA 334 + 29.71	PLUG EXISTING
1	STA 448 + 48.50	PLUG EXISTING
1	LT STA 501 + 17	TEMP 36" CMP - STAGE II
4	TOTAL	

**Z0025500 FURNISHING AND INSTALLING PROPERTY MARKERS**

EACH	LOCATION
5	Contingency
5	TOTAL

**Z0028415 GEOTECHNICAL REINFORCEMENT**

SQ YD	LOCATION	REMARKS
1,053.7	STA 40 + 10.5 - 42 50	WILLOW ROAD
857.5	STA 88 + 00 - 89 89.31	BETHEL ROAD
1,911.	TOTAL	

**Z0029001 GRATED CULVERT EXTENSION NO. 1**

EACH	LOCATION	REMARKS
2	RT/LT STA 182 + 98.97	SN 043-1063
2	TOTAL	

**Z0029002 GRATED CULVERT EXTENSION NO. 2**

EACH	LOCATION	REMARKS
1	RT STA 448 + 28.40	SN 043-1068
1	TOTAL	

**Z0029003 GRATED CULVERT EXTENSION NO. 3**

EACH	LOCATION	REMARKS
1	LT STA 484 + 22.22	SN 043-1069
1	TOTAL	

**Z0029004 GRATED CULVERT EXTENSION NO. 4**

EACH	LOCATION	REMARKS
1	LT STA 501 + 14.74	SN 043-1070
1	TOTAL	

**Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION	REMARKS
1	STA 3 + 28.83 - 3 48.83	SN 043-1062 (Stage 2)
1	STA 6 + 23.22 - 6 43.22	SN 043-1062 (Stage 2)
1	STA 6 + 48.22 - 6 68.22	SN 043-1062 (Stage 3) - Absorb 350
3	TOTAL	

**Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3**

EACH	LOCATION	REMARKS
1	STA 3 + 03.83 - 3 23.83	SN 043-1062 (Stage 3)
1	TOTAL	

**Z5100900 TURF REINFORCEMENT MAT**

SQ YD	LOCATION	REMARKS
186.4	LT STA 4 + 53.20 - 5 41.20	SN 043-1062
733.1	RT STA 183 + 21.00 - 186 00	SN 043-1063 - Along Gravel Parking Lot
919	TOTAL	

**CORRUGATED STEEL PIPE MULTIPLE END SECTIONS EQUIVALENT DOUBLE ROUND-SIZE 36"**

EACH	LOCATION	REMARKS
2	IL ROUTE 78 LT STA 182 + 40.98	FE over Channel- Twin Culverts
2	WILLOW ROAD LT STA 41 + 16.00	CE - Twin Culverts
4	TOTAL	