

EARTHWORK & ENTRANCE SCHEDULES

EARTHWORK SCHEDULE

LOCATION	EARTH EXC (CUT)	EARTH EXC ADJ SHRINK 25%	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
	CU YD	CU YD	CU YD	CU YD
1 29 - 10 50	3759	2819	1439	1380
52 50 - 56 50	575	431	376	55
177 50 - 186 50	1050	788	404	383
224 75 - 245 50	10870	8153	7682	471
274 00 - 287 00	2838	2129	2465	-337
329 50 - 350 00	2318	1739	2506	-767
401 50 - 408 00	1421	1066	895	171
434 50 - 437 00	35	26	929	-903
447 00 - 449 50	88	66	1338	-1272
482 00 - 486 00	327	245	358	-113
498 50 - 503 50	59	44	360	-316
SIDERROADS				
40 00 - 42 50	1525	1143	25	1118
0 00 - 2 75	555	416	37	380
88 00 - 90 00	555	416	416	0
TOTAL				
	25,973	19,480	19,230	250

ENTRANCE SCHEDULE

LOCATION	REMARKS	35101400		40800050	
		PROPOSED SURFACE AREA	AGGREGATE BASE COURSE TYPE B	INCIDENTAL HOT-MIX ASPHALT SURFACING	
		SQ. YD.	TON	TON	
IL ROUTE 78					
1 + 85 LT	FE	40.1	18.27	—	
5 + 30 RT	PE	40.7	21.03	5.70	
5 + 53 LT	FE	205.6	93.67	—	
52 + 85 RT	FE	124.5	56.70	—	
182 + 41 LT	FE	227.1	103.48	—	
230 + 17 RT	FE	71.3	32.47	—	
231 + 14 RT	PE	101.9	51.21	14.27	
280 + 78 RT	PE	133.7	63.79	18.72	
281 + 00 LT	FE	179.1	81.60	—	
340 + 40 RT	FE	138.7	63.16	—	
341 + 46 RT	FE	140.0	63.79	—	
347 + 68 RT	FE	154.7	70.46	—	
349 + 56 RT	FE	165.6	75.43	—	
402 + 77 RT	FE	100.4	45.76	—	
SIDERROADS					
WILLOW ROAD					
41 + 16 LT	CE	238.1	108.49	33.34	
TOTAL			949.32	72.03	