

SCHEDULE OF QUANTITIES

70300100 SHORT-TERM PAVEMENT MARKING

FOOT	LOCATION	
	US 20	
288	574+00 - 598+00	WHITE RT EDGE 3 APPLICATIONS
720	574+00 - 598+00	DOUBLE YELLOW 3 APPLICATIONS
288	574+00 - 598+00	WHITE LT EDGE 3 APPLICATIONS
288	574+00 - 598+00	WHITE SHOULDER DIAGONALS 3 APPLICATIONS

1584 TOTAL

70300610 TEMPORARY PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION	
15.6	TURN ARROWS	
15.6	TURN ARROWS	
31.2	TOTAL	

70300625 TEMPORARY PAINT PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	
	US 20	
2400	574+00 - 598+00	WHITE RT EDGE STAGE 1
4800	574+00 - 598+00	DOUBLE YELLOW STAGE 1
2400	574+00 - 598+00	WHITE LT EDGE STAGE 1
2400	574+00 - 598+00	WHITE RT EDGE STAGE 2
4800	574+00 - 598+00	DOUBLE YELLOW STAGE 2
2400	574+00 - 598+00	WHITE LT EDGE STAGE 2
2400	574+00 - 598+00	WHITE RT EDGE STAGE 3
4800	574+00 - 598+00	DOUBLE YELLOW STAGE 3
2400	574+00 - 598+00	WHITE LT EDGE STAGE 3
	IL 84	
1550	1375+00 - 1390+50	WHITE RT EDGE STAGE 3
3100	1375+00 - 1390+50	DOUBLE YELLOW STAGE 3
1550	1375+00 - 1390+50	WHITE LT EDGE STAGE 3
35000	TOTAL	

70300660 TEMPORARY PAINT PAVEMENT MARKING - LINE 24"

FOOT	LOCATION	
18	1375+00	WHITE STOP BAR
18	1374+90	WHITE STOP BAR
36	TOTAL	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	
528	SHORT TERM PAVEMENT MARKING	
6400	TEMP PAVEMENT MARKING	
6928	TOTAL	

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	
150	1381+25 - 1382+75	
150	TOTAL	

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ FT	LOCATION	
15.6	US 20 - 582+62	WHITE TURN ARROW
15.6	US 20 - 584+20	WHITE TURN ARROW
15.6	US 20 - 584+79	WHITE TURN ARROW
15.6	US 20 - 585+37	WHITE TURN ARROW
15.6	US 20 - 587+08	WHITE TURN ARROW
15.6	US 20 - 587+66	WHITE TURN ARROW
15.6	US 20 - 588+24	WHITE TURN ARROW
15.6	US 20 - 588+83	WHITE TURN ARROW
124.8	TOTAL	

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	
	EDGE OF ROADWAY	
1276	575+62 - 582+00	WHITE
1450	582+00 - 596+83	WHITE
1175	582+00 - 1383+00	WHITE
1894	596+83 - 1383+00	WHITE
	MEDIAN	
2394	575+62 - 582+00	DOUBLE YELLOW
566	582+00 - 583+42	DOUBLE YELLOW
2344	586+54 - 592+41	DOUBLE YELLOW
570	1376+30 - 1374+89	DOUBLE YELLOW
	CENTERLINE	
800	1379+00 - 1383+00	DOUBLE YELLOW
540	1376+30 - 1379+00	DOUBLE YELLOW
888	592+41 - 596+83	DOUBLE YELLOW
80	575+62 - 576+02	DOUBLE YELLOW
428	583+42 - 585+57	DOUBLE YELLOW

FOOT	LOCATION	
	PARKING LOT	
524	25 STALLS	
14929	TOTAL	

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION	
	US 20	
54	581+22 - 583+42	WHITE SKIP DASH
210	583+42 - 585+57	LEFT TURN LANE
254	586+54 - 589+03	RIGHT TURN LANE
48	589+03 - 591+23	WHITE SKIP DASH
	ISLAND	
160	OUTER	WHITE EDGE
726	TOTAL	

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	
	US 20	
223	576+02 - 583+42	YELLOW MEDIAN DIAGONAL
187	586+54 - 592+41	YELLOW MEDIAN DIAGONAL
142	575+62 - 585+00	WHITE SHOULDER DIAGONAL
	IL 84	
34	1374+88 - 1376+30	YELLOW MEDIAN DIAGONAL
	ISLAND	
127		WHITE DIAGONALS
713	TOTAL	

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION	
18	1375+02	WHITE STOP BAR
12	1374+89	WHITE STOP BAR
30	TOTAL	

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	
	US 20	
55	575+62 - 585+57	TWO WAY AMBER
41	586+54 - 596+83	TWO WAY AMBER
11	583+42 - 585+57	ONE WAY CRYSTAL
13	586+54 - 589+03	ONE WAY CRYSTAL
	IL 84	
24	1374+88 - 1383+00	TWO WAY AMBER
144	TOTAL	

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION	
	IL 84	
250	1383+00 - 1390+50	EDGE LINE
500	1383+00 - 1390+50	DOUBLE CENTERLINE
250	1383+00 - 1390+50	EDGE LINE
	US 20	
800	574+00 - 598+00	EDGE LINE
1600	574+00 - 598+00	DOUBLE CENTERLINE
800	574+00 - 598+00	EDGE LINE
4200	TOTAL	

80400100 ELECTRIC SERVICE INSTALLATION

EACH	LOCATION	
1	US 20/ IL 84	
1	TOTAL	

81020500 CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL

FOOT	LOCATION	
80	586+80	
80	575+20	
160	TOTAL	

81603000 UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE

FOOT	LOCATION	
380	SERVICE TO POLES	
380	TOTAL	

81900200 TRENCH AND BACKFILL FOR ELECTRICAL WORK

FOOT	LOCATION	
200	IL 84 1375+20	
200	TOTAL	

82102250 LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT

EACH	LOCATION	
1	584+98, 31 LT	
1	586+32, 77 LT	
1	586+77, 41 RT	
3	TOTAL	

82500605 LIGHTING CONTROLLER PHOTOCELL RELAY

EACH	LOCATION	
1	IL 84 - 1375+28 90' LT	
1	TOTAL	

83008600 LIGHT POLE, ALUMINUM, 40 FT. M.H., 15 FT. MAST ARM

EACH	LOCATION	
1	584+98, 31 LT	
1	586+32, 77 LT	
1	586+77, 41 RT	
3	TOTAL	

83600300 LIGHT POLE FOUNDATION, 30" DIAMETER

FOOT	LOCATION	
6	584+98, 31 LT	
6	586+32, 77 LT	
6	586+77, 41 RT	
18	TOTAL	

83800650 BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN

EACH	LOCATION	
4	584+98, 31 LT	
4	586+32, 77 LT	
4	586+77, 41 RT	
12	TOTAL	

XX005938 SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)

EACH	LOCATION	
1	IL 84 - 1374+82 LT	STOP SIGN
1	IL 84 - 1381+00 LT	STOP AHEAD SIGN
2	TOTAL	

XX005896 CONCRETE PAD REMOVAL

SQ FT	LOCATION	
141	IL 84 - 1375+36 7' RT	
160	IL 84 - 1375+65 0' RT	
11	IL 84 - 1375+48 23' RT	
139	IL 84 - 1376+49 23' RT	
451	TOTAL	

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SQ YD	LOCATION	
	US 20	
11	578+00 LT, RT	
11	580+77 LT, RT	
11	583+00 LT, RT	
11	585+30 LT, RT	
11	586+30 LT, RT	
11	589+00 LT, RT	
11	591+50 LT, RT	
11	594+00 LT, RT	
11	596+50 LT, RT	

SQ YD	LOCATION	
	IL 84	
11	1375+50 LT, RT	
11	1378+00 LT, RT	
11	1380+00 LT, RT	
11	1382+50 LT, RT	
143	TOTAL	

X0712400 TEMPORARY PAVEMENT

SQ YD	LOCATION	
3759	IL 84 - 1374+00 - 1390+50	
3759	TOTAL	

X0919000 TEMPORARY PAVEMENT REMOVAL

SQ YD	LOCATION	
3759	IL 84 - 1374+00 - 1390+50	
3759	TOTAL	

X4402200 PAVEMENT REMOVAL (CONCRETE)

SQ YD	LOCATION	
214	590+36 - 592+53 LT	PARKING LOT
214	TOTAL	

Z0018700 DRAINAGE STRUCTURE TO BE REMOVED

EACH	LOCATION	
1	584+30, 35' LT	
1	TOTAL	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	
1	IL 84 - 1381+00	
1	IL 84 - 1383+00	
2	TOTAL	

Z0055100 RUMBLE RESURFACING

SQ YD	LOCATION	
33.3	1378+00	
33.3	1380+00	
33.3	1383+00	
100	TOTAL	

FILE NAME =	USER NAME = IDOTCAD	DESIGNED - SPF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
W:\2298-03 - US 20 IL 84 Intersection	DD Sheets\0208108-shr-SCH.dgn	DRAWN - AJP	REVISED -					301	30-M-2	JoDAVIESS	81	10
PLOT SCALE = 1:80000 ' / IN.	CHECKED - JMS	REVISED -						CONTRACT NO. 64E29				
PLOT DATE = 1/21/2009	DATE - 01/23/09	REVISED -						SCALE:	SHEET NO. 02 OF 02 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.