SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	URBAN 90% FED / 10% STATE HSIP SFTY-4A	URBAN 90% FED / 10% STATE HSIP Y031-1F
	67100100	MOBILIZATION	L SUM	1	1	
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
	70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10	
	70300220	TEMPORARY PAVEMENT MARKING LINE - 4"	FOOT	6914	6,914	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2305	2,305	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	265	265	
*	78000200	THERMOPLASTIC PAVEMENT MAKING - LINE 4"	FOOT	3349	3,349	
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	2352	2,352	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	225	225	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	73	73	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	108	108	
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	461	461	
*	81306500	REMOVE EXISTING JUNCTION BOX	EACH	1		1
*	81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP TYPE USE) 1/C No. 10	FOOT	884		884
*	82103900	LUMINAIRE SODUIM VAPOR, MULTI-MOUNT, 250 WATT	EACH	2		2
*	82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1		1
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	1014		1014
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1524		1524
*	87700280	STEEL MAST-ARM ASSEMBLY AND POLE, 48 FT.	EACH	2		2
*	87900200	DRILL EXISITNG HANDHOLE	EACH	16		16
*	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4

* SPECIALTY ITEMS