

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION	OFFSET	REMARKS
6	42+50 TO 43+50	LT	19' Spacing
3	43+00 TO 44+00	RT	63' Spacing
2	43+50 TO 44+50	LT	94' Spacing
2	44+00 TO 46+00	RT	250' Spacing
4	44+50 TO 45+50	LT	35' Spacing
1	45+50 TO 46+00	LT	250' Spacing
18	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION	OFFSET	REMARKS
301	38+66 TO 41+50	LT	Along Construction Limits
150	50+50 TO 52+00	RT	Along Construction Limits
212	68+00 TO 70+12	RT	Along Construction Limits
663	TOTAL		

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION	OFFSET	REMARKS
1	41+06	LT	
1	69+18	RT	
2	TOTAL		

31100910 SUB-BASE GRANULAR MATERIAL, TYPE A 12"

SQ YD	LOCATION	OFFSET	REMARKS
182.0	1428+13 TO 1429+69	RT	INTERSTATE 10' SHOULDER
2607.0	38+66 TO 47+35	LT & RT	RAMP B
5945.5	47+35 TO 70+12	RT	RAMP B
8734.5	TOTAL		

40603310 HOT MIX ASPHALT SURFACE COURSE, MIX "C", N 50

TON	LOCATION	OFFSET	REMARKS
18.3	1428+13 TO 1429+69	RT	INTERSTATE 10' SHOULDER
43.3	38+66 TO 47+35	LT	RAMP B 4' SHOULDER
234.9	38+66 TO 70+12	RT	RAMP B 6' SHOULDER
23.9	46+00 TO 47+35	LT	PAVED GORE AREA
320.4	TOTAL		

40701961 HOT MIX ASPHALT PAVEMENT(FULL-DEPTH), 14"

SQ YD	LOCATION	OFFSET	REMARKS
2307.6	38+66 TO 51+64		16' WIDE
383.8	47+35 TO 50+64		17' TO 4' GORE AREA
33.3	50+64 TO 51+64		4' TO 2' GORE AREA
466.7	51+64 TO 54+64		16' TO 12'
1332.0	54+64 TO 64+63		12' WIDE
396.5	64+63 TO 70+12		12' TO 1'
4919.9	TOTAL		

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION	OFFSET	REMARKS
2130.1	38+66 TO 50+64		16' WIDE
466.7	50+65 TO 54+64		20' TO 1' WIDE
2597	TOTAL		

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION	OFFSET	REMARKS
311.1	1428+13 TO 1430+93	RT	INTERSTATE 10' SHOULDER
414.6	38+66 TO 48+00	LT	RAMP B 4' SHOULDER
3628.4	38+66 TO 70+12	RT	RAMP B 6' & 10' SHOULDERS
4354.1	TOTAL		

48100100 AGGREGATE SHOULDERS, TYPE A

TON	LOCATION	OFFSET	REMARKS
73.6	38+66 TO 46+00	LT	
315.3	38+66 TO 70+12	RT	
388.9	TOTAL		

48203021 HOT - MIX ASPHALT SHOULDERS, 6"

SQ YD	LOCATION	OFFSET	REMARKS
163.3	1428+13 TO 1429+69	RT	INTERSTATE 10' SHOULDER
386.2	38+66 TO 47+35	LT	RAMP B 4' SHOULDER
2097.3	38+66 TO 70+12	RT	RAMP B 6' SHOULDER
213.8	46+00 TO 47+35	LT	PAVED GORE AREA
2860.6	TOTAL		

50800105 REINFORCEMENT BARS

POUND	LOCATION	OFFSET	REMARKS
6890	1428+50	RT	DOUBLE 12' X 6' BOX CULVERT
4350	1451+47	RT	DOUBLE 8' X 5' BOX CULVERT
11240	TOTAL		