

SUMMARY OF QUANTITIES		100% FEDERAL			
CODE NO.	ITEM	CONSTRUCTION CODE: 1000			
		UNIT	TOTAL QUANTITY	GRUNDY COUNTY	LIVINGSTON COUNTY
20400800	FURNISHED EXCAVATION	CU YD	56		56
25100630	EROSION CONTROL BLANKET	SQ YD	1176		1176
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	39528	1337	38191
40600300	AGGREGATE (PRIME COAT)	TON	1217	42	1175
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	91	3	88
40600535	LEVELING BINDER (HAND METHOD), N70	TON	151	5	146
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	12718	416	12302
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600990	TEMPORARY RAMP	SQ YD	1077	79	998
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	25257	889	24368
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1225	25	1200
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2010		2010
42400800	DETECTABLE WARNING	SQ FT	224		224
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	273370	9669	263701
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	33218		33218
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1092	286	806
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	198		198
44000600	SIDEWALK REMOVAL	SQ FT	2010		2010
44003100	MEDIAN REMOVAL	SQ FT	200		200
44200988	CLASS B PATCHES, TYPE IV, 11 INCH	SQ YD	380	380	
44213100	PAVEMENT FABRIC	SQ YD	380	380	
44213200	SAW CUTS	FOOT	710	710	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	8995		8995
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	198		198
60623711	CONCRETE MEDIAN	SQ FT	200		200
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	30		30
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5		5
67100100	MOBILIZATION	L SUM	1	0.1	0.9
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.1	0.9
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1		1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	

FILE NAME =	USER NAME = schwanke	DESIGNED -	REVISED -
ct:\pw\work\VPWIDOT\SCHWANKER\0119033\666753-sht-soq.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Feb 11, 2009 - 02:40:12 PM		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
326	(119,120,121,122,123)RS-3	GRU & LIV	36	3
CONTRACT NO. 66753			ILLINOIS FED. AID PROJECT	