

MEDIAN, CURB, & SIDEWALK SCHEDULE								
DESCRIPTION	LOCATION NUMBER	COMB CURB & GUTTER REM	MEDIAN REM	SIDEWALK REM	CCC&G TYPE B-6.24	PCC SIDEWALK 4"	CONCRETE MEDIAN	DETECTABLE WARNING
		FOOT	SQ FT	SQ FT	FOOT	SQ FT	SQ FT	SQ FT
WAUPANSIE ST	1	10		90	10	90		8
	2	10		90	10	90		8
SEMINOLE ST	3	10		125	10	125		8
	4	10		90	10	90		8
IL RTE 17	5	12		125	12	125		8
	6	12		90	12	90		8
	7		50				50	16
	8		50				50	16
	9		50				50	16
	10		50				50	16
	11	12		90	12	90		8
	12	10		90	10	90		8
DELAWARE ST	13	10		90	10	90		8
	14	8		125	8	125		8
ORCHARD RD	15	10		90	10	90		8
	16	10		90	10	90		8
CHIPPEWA ST	17	10		90	10	90		8
	18	8		125	8	125		8
SOUTH ST	19	10		90	10	90		8
	20	8		125	8	125		8
SMITH LANE	21	10		90	10	90		8
	22	10		90	10	90		8
JAMES ST	23	10		90	10	90		8
	24	8		125	8	125		8
<b>TOTALS</b>		<b>198</b>	<b>200</b>	<b>2010</b>	<b>198</b>	<b>2010</b>	<b>200</b>	<b>224</b>

RUMBLE STRIP SCHEDULE	
STATION	RUMBLE STRIP EACH
	743+70, SBL
752+02, SBL	1
754+02, SBL	1
<b>TOTAL</b>	<b>3</b>

CLASS B PATCHES 11"								
STATION	TO	STATION	LANE	TYPE IV	PAVEMENT FABRIC	DOWEL BARS	TIE BARS	SAW CUTS
				SOYD	SOYD	EACH	EACH	FOOT
130+79	TO	129+89	SBOL	120	120	70	45	204
130+79	TO	129+89	SBPL	120	120	70	90	204
130+79	TO	129+89	SBTL	120	120	70	45	204
130+34	TO	129+89	MEDIAN	20	20	8	22	96
<b>TOTALS</b>				<b>380</b>	<b>380</b>	<b>218</b>	<b>202</b>	<b>710</b>