SEEDING AND EROSION CONTROL SCHEDULE

LOCATION			SIDE	SEEDING, CLASS 3	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	TEMPORARY EROSION CONTROL SEEDING	EROSION CONTROL BLANKET	PERIMETER EROSION BARRIER	INLET AND PIPE PROTECTION	TEMPORARY DITCH CHECKS
STATION	TO	STATION	LT/RT	(ACRE)	(POUND)	(POUND)	(POUND)	(POUND)	(SQ YD)	(FOOT)	(EACH)	(EACH)
47+00.00	TO	54+00.00	LT	0.30	27	27	27	30	1461			
47+00.00	TO	54+00.00	RT	0.30	26	26	26	30	1404			
47+85.00			LT									1
47+90.00			LT								1	
48+30.00			RT									1
48+40.00			RT								1	
49+50.00			RT									1
49+50.00			LT									1
50+40.59			RT						44			
50+40.66			LT						61			
50+48.00			RT									1
50+48.00			LT									1
50+62.00			RT									1
50+62.00			LT									1
51+75.00			RT									1
51+75.00			LT									1
NE OF CULVERT			LT							13		
SE OF CULVERT			LT							8		
NW OF CULVERT			RT							13		
SW OF CULVERT			RT							8		
TOTAL				0.60	53	53	53	60	2,970	42	2	10

MAINTENANCE OF TRAFFIC

STAGE	LOCATION			SIDE	SHORT TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING-LINE 4"	TEMPORARY PAVEMENT MARKING-LINE 6"	WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
					WIDTH	WHITE	WHITE	YELLOW					
	STATION	TO	STATION	LT/RT	(IN)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(EACH)	(EACH)
	46+10.00	TO	54+90.00	LT			880						
	46+10.00	TO	54+90.00	RT			880						
	46+10.00	TO	54+90.00	CL				220					
STAGE I	47+35.00			RT	24	12			24				
	47+45.00	TO	53+65.00	RT	4	620			207				
	48+60.00	TO	52+50.00	LT	4	390			130				
	49+25.00											1	
	49+25.00	TO	51+77.00							253			
	51+77.00											1	
	53+75.00			LT	24	12			24				
STAGE II	47+45.00	TO	53+65.00	LT	4	620			207				
	48+60.00	TO	52+50.00	RT	4	390			130				
	49+32.00												1
	49+32.00	TO	51+85.00								253		
	51+85.00												1
TOTAL						2,044	1,760	220	722	253	253	2	2

EARTHWORK SCHEDULE

STATION		SIDE	CUT VOLUME	FILL VOLUME
			EARTH EXCAVATION	FURNISHED EXCAVATION
FROM	TO	LT/RT	(CU YD)	(CU YD)
47+00.00	54+00.00	LT	690.00	495.00
47+00.00	54+00.00	RT	490.00	320.00
TOTAL			1,180.00	815.00

WOVEN WIRE FENCE SCHEDULE

LOCATION			SIDE	WOVEN WIRE FENCE REMOVAL	WOVEN WIRE FENCE, 4'	TEMPORARY FENCE
STATION	TO	STATION	LT/RT	(FOOT)	(FOOT)	(FOOT)
47+00.00	TO	48+21.54	RT	122	122	122
48+80.14	TO	49+35.12	RT	55		
48+80.14	TO	50+37.06	RT		157	157
49+82.22	TO	50+25.86	RT	44		
50+86.32	TO	51+60.23	RT	74		
50+86.32	TO	51+64.07	RT		78	78
TOTAL				295	357	357

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

LOCATION	EACH
STATION	
46+75.00, 30' LT	1
47+50.00, 45' LT	1
50+00.00, 45' LT	1
50+25.00, 40' LT	1
53+00.00, 40' LT	1
54+00.00, 29.07' LT	1
47+00.00, 30' RT	1
47+50.00, 35' RT	1
51+00.00, 35' RT	1
51+50.00, 40' RT	1
53+00.00, 40' RT	1
54+00.00, 31.10' RT	1
TOTAL	12

PAVEMENT MARKING SCHEDULE

LOCATION			SIDE	PAINT PAVEMENT MARKING-LINE 4"	PAINT PAVEMENT MARKING-LINE 6"
				WHITE	YELLOW SKIP DASH
STATION	TO	STATION	LT/RT	(FOOT)	(FOOT)
46+10.00	TO	54+90.00	LT	880	
46+10.00	TO	54+90.00	RT	880	
46+10.00	TO	54+90.00	CL		220
TOTAL				1,760	220

TEMPORARY BRIDGE TRAFFIC SIGNALS

	(EACH)
	1
TOTAL	1

TREE REMOVAL (6 TO 15 UNITS DIAMETER)

STATION	OFFSET (FOOT)	LT/RT	UNITS
49+77.81	34.0	RT	6
49+80.93	33.0	RT	8
50+09.07	33.0	RT	8
50+12.42	38.0	LT	10
51+25.12	33.0	RT	6
51+38.15	34.0	RT	8
51+98.63	32.0	RT	6
52+91.69	34.0	RT	6
	TOTAL		58

TREE TRUNK PROTECTION

STATION	OFFSET (FOOT)	LT/RT	EACH
47+73.55	35.0	RT	1
51+23.98	35.0	RT	1
51+75.46	38.0	RT	1
53+86.07	34.0	RT	1
53+86.07	34.0	RT	1
	TOTAL		5

TREE PRUNING (1 TO 10 INCH DIAMETER)

STATION	OFFSET (FOOT)	LT/RT	EACH
47+73.55	35.0	RT	1
51+23.98	35.0	RT	1
51+75.46	38.0	RT	1
53+86.07	34.0	RT	1
53+86.07	34.0	RT	1
	TOTAL		5

PLAN — SURVEYED / PLOTTED / ALIGNMENT CHECKED / RT. OF WAY CHECKED / CADD FILE NAME — NOTE BOOK NO. — BY — DATE

PROFILE — SURVEYED / PLOTTED / GRADES CHECKED / STRUCTURE NOTATNS CHKD — NOTE BOOK NO. — BY — DATE

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED DB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES SN 027-2552 SHEET 2 OF 2
		DRAWN NS/RM	REVISED -		
	PLOT SCALE = $SCALE$	CHECKED AS	REVISED -		
	PLOT DATE = $DATE$	DATE MARCH 2009	REVISED -		SCALE: NONE / SHEET NO. 1 OF SHEETS / STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
697	(17)I	FORD	29	7
		CONTRACT NO. 66874		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		