

SUMMARY OF QUANTITIES				80/20 FED / STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
				ROADWAY I000
20400800	FURNISHED EXCAVATION	CU YD	35	35
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8042	8042
40600300	AGGREGATE (PRIME COAT)	TON	204	204
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30	30
40600535	LEVELING BINDER (HAND METHOD), N70	TON	50	50
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	4286	4286
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600990	TEMPORARY RAMP	SQ YD	64	64
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	8571	8571
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	269	269
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	103473	103473
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2861	2861
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	21	21
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	12400	12400
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	61988	61988
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	7749	7749
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1025	1025
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	61988	61988
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	7749	7749
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	388	388
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	388	388

* SPECIALTY ITEMS

FILE NAME =	USER NAME = bbraboypc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\braboypc\d0107230\d369111-shr-plans.dgn	DRAWN -	REVISED -	317			(20,21)RS-5	IROQUOIS	6	3	
PLOT SCALE = 53.4183' / IN.	CHECKED -	REVISED -	CONTRACT NO. 66911							
PLOT DATE = Jan 12, 2009 - 01:36:41 PM	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	