

# SUMMARY OF QUANTITIES

ROUTE		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P.	665	142 RS-6; 143RS-4	FULTON	76	4
MKD.	IL 116				

\* 142 RS-6; 143[RS-4, (C-3)BR]; 142X(C-1)I

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNITS	CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	80% FED. 20% STATE 1000
20200100	EARTH EXCAVATION	CU YD	1,285	1,285
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	46	46
20700220	POROUS GRANULAR EMBANKMENT	CU YD	64	64
20800150	TRENCH BACKFILL	CU YD	445	445
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	334	334
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,804	2,804
* 25000300	SEEDING, CLASS 3	ACRE	0.58	0.58
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	52	52
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	52	52
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	52	52
* 25100115	MULCH, METHOD 2	ACRE	0.4	0.4
* 25100630	EROSION CONTROL BLANKET	SQ YD	913	913
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	58	58
28000300	TEMPORARY DITCH CHECKS	EACH	14	14
28000310	AGGREGATE DITCH CHECKS	EACH	1	1
28000400	PERIMETER EROSION BARRIER	FOOT	510	510
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100107	STONE RIPRAP, CLASS A4	SQ YD	356	356
28200200	FILTER FABRIC	SQ YD	356	356
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	823	823
35501323	HOT-MIX ASPHALT BASE COURSE, 9 3/4"	SQ YD	365	365
35800100	PREPARATION OF BASE	SQ YD	71	71
35800200	AGGREGATE BASE REPAIR	TON	32	32
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	66	66
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1349	1349
40600990	TEMPORARY RAMP	SQ YD	245	245
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	10,445	10,445
40800030	AGGREGATE (PRIME COAT)	TON	382	382
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	476	476
44000100	PAVEMENT REMOVAL	SQ YD	361	361
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	123,683	123,683
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2,089	2,089
44004250	PAVED SHOULDER REMOVAL	SQ YD	167	167
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	285	285
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	264	264
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	149	149
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	66,106	66,106

CODE NO.	SUMMARY OF QUANTITIES ITEM	UNITS	CONSTRUCTION TYPE CODE	
			TOTAL QUANTITY	80% FED. 20% STATE 1000
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,784	1,784
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	402	402
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1
50102400	CONCRETE REMOVAL	CU YD	31	31
50800105	REINFORCEMENT BARS	POUND	25,333	25,333
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12,391	12,391
50800515	BAR SPLICERS	EACH	51	51
51500100	NAME PLATES	EACH	2	2
54002020	EXPANSION BOLTS 3/4 INCH	EACH	98	98
54003000	CONCRETE BOX CULVERTS	CU YD	241	241
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	325	325
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	50	50
* 66700605	PERMANENT SURVEY TIES	EACH	16	16
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3
63200310	GUARDRAIL REMOVAL	FOOT	250	250
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	3	3
66700205	PERMANENT SURVEY MARKERS, TYPE 1	EACH	4	4
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	40	40
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	11,989	11,989
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	109,970	109,970
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,056	1,056
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,549	1,549
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	64	64
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3,168	3,168
70400100	TEMPORARY CONCRETE BARRIER	FOOT	340	340
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94	94
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	109,970	109,970
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	1,056	1,056
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	1,549	1,549
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	64	64

\* SPECIALTY ITEM