

SCHEDULE OF QUANTITIES

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 665	142 RS-6; 143RS-4	FULTON	76	14
MKD. IL 116				

* 142 RS-6; 143[RS-4, (C-3)BR]; 142X(C-1)I

EXPANSION BOLTS 3/4 INCH	
London Mills: LT-RT Sta. 23+70.39	98 EACH
TOTAL =	98 EACH

TEMPORARY CONCRETE BARRIER	
IL 116: Sta. 238+84 to 242+24	340 FT
TOTAL =	340 FT

TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	
IL 116: Sta. 240+54.87	1 EACH
TOTAL =	1 EACH

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	
IL 116: LT Sta. 240+10.39 to 240+60.39	50 FT
IL 116: LT Sta. 240+85.39 to 241+60.39	75 FT
IL 116: RT Sta. 238+77 to 240+27	150 FT
IL 116: RT Sta. 240+52 to 241+02	50 FT
TOTAL =	325 FT

RELOCATE TEMPORARY CONCRETE BARRIER	
IL 116: Sta. 239+55 to 241+55	200 FT
TOTAL =	200 FT

SEEDING, CLASS 3	
IL 116: LT Sta. 238+75 to 242+25	0.22 ACRE
IL 116: RT Sta. 238+00 to 241+75	0.28 ACRE
London Mills: LT Sta. 23+00 to 24+25	0.03 ACRE
London Mills: RT Sta. 23+25 to 24+58	0.05 ACRE
TOTAL =	0.58 ACRE

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	
IL 116: LT Sta. 239+60.39 to 240+10.39	1 EACH
IL 116: RT Sta. 238+27 to 238+77	1 EACH
IL 116: RT Sta. 241+02 to 241+52	1 EACH
TOTAL =	3 EACH

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	
IL 116: RT Sta. 239+55	1 EACH
IL 116: RT Sta. 241+55	1 EACH
TOTAL =	2 EACH

NITROGEN FERTILIZER NUTRIENT	
IL 116: Sta. 238+00 to 242+25	45 POUND
London Mills: Sta. 23+00 to 24+58	7 POUND
TOTAL =	52 POUND

SPB GUARD RAIL, ATTACHED TO STRUCTURES	
IL 116: LT Sta. 240+60.39 to 240+85.39	25 FT
IL 116: RT Sta. 240+27 to 240+52	25 FT
TOTAL =	50 FT

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
IL 116: RT Sta. 238+84	1 EACH
IL 116: RT Sta. 242+24	1 EACH
TOTAL =	2 EACH

PHOSPHORUS FERTILIZER NUTRIENT	
IL 116: Sta. 238+00 to 242+25	45 POUND
London Mills: Sta. 23+00 to 24+58	7 POUND
TOTAL =	52 POUND

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
London Milsl: RT 33' Sta. 23+50	1 EACH
London Milsl: RT 45' Sta. 23+75	1 EACH
London Milsl: RT 45' Sta. 24+25	1 EACH
TOTAL =	3 EACH

MULCH, METHOD 2	
IL 116: LT Sta. 238+75 to 242+25	0.13 ACRE
IL 116: RT Sta. 238+00 to 241+75	0.22 ACRE
London Milsl: RT Sta. 23+25 to 24+58	0.05 ACRE
TOTAL =	0.4 ACRE

POTASSIUM FERTILIZER NUTRIENT	
IL 116: Sta. 238+00 to 242+25	45 POUND
London Mills: Sta. 23+00 to 24+58	7 POUND
TOTAL =	52 POUND

BAR SPLICERS	
IL 116: Sta. 240+54.87	51 EACH
TOTAL =	51 EACH

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. NONE
HORIZ. NONE
DATE 9/19/2003

DRAWN BY LCE
CHECKED BY