

COMMITMENTS

No commitments have been made for this project.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VARIOUS	D4 BRIDGE PAINTING 2009	TAZEWELL	12	2

GENERAL NOTES

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Structural Steel". All beams, bearings and other structural steel shall be cleaned per Near White Blast Cleaning- SSPC-SP10 according to the following schedule.

Bridge No. 1 - 3, Entier Structrue

The The designated Paint System shall be Paint System 5 - MCU.

The Finish Coat for the Interior and Exterieur shall be according to the following schedule:

Bridge No. 1 - 3, All outside fascias and bottom of the bottom flange shall be Blue (Munsell No. 10B 3/6)
All Underside shall be painted Light Gray (Munsell No. 5B 7/1)

AIR MONITORS

STRUCTURE 090-0131 - 0
STRUCTURE 090-0095 - 1
STRUCTURE 090-0053 - 1

QP1 & QP2 ARE REQUIREMENTS FOR THIS PROJECT

**COMMITMENTS &
GENERAL NOTES**