

LOCATION OF WORK:

MCLEAN COUNTY
 STRUCTURE
 IMPROVEMENTS
 S.N. 057-0202
 FAS 676 (US 150)
 STA. 189+89.00
 100% STATE
 STA. 196+46.00

CONSTRUCTION TYPE CODE:

SFTY-2A
 TOTAL
 QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	76.0
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	494.0
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	62.0
50102400	CONCRETE REMOVAL	CU YD	31.9
50157300	PROTECTIVE SHIELD	SQ YD	95.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	32.3
50300300	PROTECTIVE COAT	SQ YD	1,300.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3,150.0
50800515	BAR SPLICERS	EACH	42.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	269.0
58600100	SAND BACKFILL	CU YD	60.0
59100100	GEOCOMPOSITE WALL DRAIN *	SQ YD	2.0
60605000	COMBINATION CONCRETE CURB AND GUTTER,TYPE B-6.24	FOOT	76.0
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	494.0
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1.0

*ELASTOMERIC MAT AND EXPANSION JOINT WORK IS INCLUDED IN THE COST OF THE GEOCOMPOSITE WALL DRAIN, SEE SHEET 11 FOR DETAILS

(CONT'D NEXT PAGE)

* SPECIALTY ITEM

FILE NAME =	USER NAME = sharerjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwwid\DOT\SHERERJM\dms83928\70	731Summary.dgn	DRAWN - JMS	REVISED -		676	19-11BJR	MCLEAN	17	4				
PLOT SCALE = 100.0000 / / IN.	CHECKED - JMS	REVISED -			CONTRACT NO. 70731								
PLOT DATE = 1/30/2009	DATE - 090308	REVISED -			SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			