

SCHEDULE OF QUANTITIES

TABULATION OF CLASS A PATCH, 10 INCH

I-39 MAINLINE (NORTHBOUND)

STATION	LOCATION	LANE	LENGTH	WIDTH	TYPE I	TYPE II	TYPE III	TYPE IV	SAWCUTS	TIE BARS	PATCHING REINFORCEMENT
					44200549 (SQ.YD.)	44200553 (SQ.YD.)	44200557 (SQ.YD.)	44200559 (SQ.YD.)	44213200 (FT)	Z0075300 (EACH)	44213000 (SQ.YD.)
475+79.00	I-39 MAINLINE	NBDL	6.0	12.0	-	8.0	-	-	66.0	-	8.0
448+13.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
381+36.00	I-39 MAINLINE	NBDL	6.0	12.0	-	8.0	-	-	66.0	-	8.0
376+37.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
372+50.00	I-39 MAINLINE	NBDL	20.0	6.0	-	13.3	-	-	84.0	20.0	13.3
360+81.00	I-39 MAINLINE	NBDL	8.0	6.0	-	5.3	-	-	48.0	-	5.3
357+31.00	I-39 MAINLINE	NBDL	6.0	12.0	-	8.0	-	-	66.0	-	8.0
352+50.00	I-39 MAINLINE	NBDL	10.0	12.0	-	13.3	-	-	78.0	-	13.3
341+50.00	I-39 MAINLINE	NBDL	8.0	6.0	-	5.3	-	-	48.0	-	5.3
339+85.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
339+36.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
334+46.00	I-39 MAINLINE	NBDL	12.0	12.0	-	-	16.0	-	84.0	-	16.0
300+00.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
287+91.00	I-39 MAINLINE	NBDL	8.0	12.0	-	10.7	-	-	72.0	-	10.7
287+10.00	I-39 MAINLINE	NBDL	6.0	12.0	-	8.0	-	-	66.0	-	8.0
285+49.00	I-39 MAINLINE	NBDL	10.0	6.0	-	6.7	-	-	54.0	-	6.7
285+01.00	I-39 MAINLINE	NBDL	15.0	6.0	-	10.0	-	-	69.0	-	10.0
278+30.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
277+09.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
273+33.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
272+88.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
272+28.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
267+90.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
264+72.00	I-39 MAINLINE	NBDL	6.0	12.0	-	8.0	-	-	66.0	-	8.0
262+90.00	I-39 MAINLINE	NBDL	6.0	10.0	-	6.7	-	-	58.0	-	6.7
261+97.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
258+18.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
256+85.00	I-39 MAINLINE	NBDL	40.0	6.0	-	-	-	26.7	144.0	40.0	26.7
256+19.00	I-39 MAINLINE	NBDL	6.0	6.0	4.0	-	-	-	42.0	-	4.0
PAGE SUBTOTALS OF CLASS A PATCH, 10 INCH					56.0	111.3	16.0	26.7	1657.0	60.0	210.0

FILE NAME =	USER NAME = blackrt	DESIGNED -	REVISED -
ct:\pw\work\PWIDOT\BLACKRT\dms84829\0570739-SHT-SCHEDULE.dgn		DRAWN JJB	REVISED -
	PLOT SCALE = 40.0177' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/23/2009	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NA SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D5 PATCHING 2009-2	MCLEAN	25	15
CONTRACT NO. 70739			ILLINOIS FED. AID PROJECT	